

# 107,65

TO: ✓  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-141-20410-00-00  
Spot: NE SW NE Sec/Township/Range 32-09-12W  
3488 feet from S Section Line  
1497 feet from E Section Line  
Lease/Unit Name: Kendig Well Number: A-1

County: Osborne Total Vertical Depth: 3297 feet

Operator License No.: 3956  
Operator Name: Brungardt Oil & leasing  
Address: P.O.Box 871  
Russell, Kansas 67665

String	Size	Depth (ft)	Pulled (ft)
Conductor			
Surface	<u>8.625"</u>	<u>212'</u>	<u>0' w/ 165sx</u>
Production	<u>5.5"</u>	<u>3290</u>	<u>2464' w/165sx</u>
Liner			

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/07/2010 10:00

Plug Co. License No.: 6426 Plug Co. Name: Express Well Services

Proposal Rcvd. from: Gary Brungardt Company: Same Phone: 785-483-4975

Proposed  
Plugging  
Method

**350SX OF 60/40 POZ CEMENT 4% GEL**  
**600# of HULLS**

**CUT CASING @ 2464'** **NO CARD NEW WELL**

Plugging Proposal Received By: Ray Dinkel Witness Type: All Partial Not Witnessed

Date/Time Plugging Completed: 09/07/2010 5:30 KCC Agent: Ray Dinkel

Actual Plugging Report:

**RT TO 3230' PUMPED 25SX OF CEMENT**  
**PT OUT AND CUT CASING @ 2464'**  
**PC TO 1650' PUMPED 125 SX OF CEMENT W/ 300# OF HULLS**  
**PC TO 1050' PUMPED 40SX OF CEMENT W/ 100# OF HULLS**  
**PC TO 570' PUMPED 60SX OF CEMENT W/ 200# OF HULLS**  
**PC TO 200' PUMPED 60SX OF CEMENT AND CIRCULATED CEMENT**  
**POOH CELLAR AND HOLE STAY FULL.**

*12/07/10*  
*2011060305*

**RECEIVED**  
**OCT 01 2010**  
**KCC WICHITA**

Remarks: Allied Cementing Ticket # 41976 GPS: 39.22951, -098.68141

Plugged through: TBG. AND CSG.

District: 04

Signed Ray A. O. K. P.  
(TECHNICIAN) ✓