

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-20173-00-00
Spot: NE Sec/Twnshp/Rge: 30-32S-40W
3886 feet from S Section Line, 1498 feet from E Section Line
Lease Name: MONTGOMERY Well #: 30-1
County: MORTON Total Vertical Depth: 2350 feet

Operator License No.: 8294
Op Name: STROMQUIST, C. DALE, A GENERAL P
Address: 1210 N. PROSPECT
LIBERAL, KS 67901

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|-----------------|
| CIBP | | 2200 | | WITH 2 SX CMT |
| SURF | 8.625 | 513 | | WITH 275 SX CMT |
| PROD | 5.5 | 2341 | 845 | WITH 100 SX CMT |

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/18/2010 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: RODNEY GONZALES Company: _____ Phone: _____

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING

Plugging Proposal Received By: STEVE DURRANT
Date/Time Plugging Completed: 08/18/2010 3:30 PM

Witness Type: COMPLETE (100%)
KCC Agent: JACK MACLASKEY

Actual Plugging Report:

CIBP @ 2200' WITH 2 SX CMT. PERFORATE 5 1/2" @ 1550'. PUMP 50 SX CMT AT 1559'. PUMP 50 SX CMT AT 550'. GOOD CIRCULATION WHILE PUMPING CMT, WELL ON VACUUM. SHUT DOWN FOR 2 HOURS. TAGGED TOC @ 550'. PUMP 50 SX CMT AT 530'. HELD OK. PUMP 15 SX CMT AT 40'.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 2300 | 2308 | | |
| 2258 | 2271 | | |

Inv. dt: 12/3/10
Inv. no: 20110602-38

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

RECEIVED
SEP 01 2010
KCC WICHITA

District: 01

RECEIVED
AUG 26 2010
KCC DODGE CITY

Signed

Jack MacLaskey
(TECHNICIAN)

Form 123