

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-19282-00-01
Spot: SWNENWNE Sec/Twnshp/Rge: 7-9S-18W
4632 feet from S Section Line, 1700 feet from E Section Line
Lease Name: WERNER Well #: 1
County: ROOKS Total Vertical Depth: 3768 feet

Operator License No.: 34179
Op Name: THOMAS M. BROWN LLC
Address: PO BOX 250
PLAINVILLE, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	200	0	125 SX
DVT		1457		400 SX
PROD	5.5	3636	0	125 SX

Well Type: SWD UIC Docket No: D21380.0 Date/Time to Plug: 06/25/2010 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: JAKE BROWN Company: THOMAS M. BROWN LLC Phone: (785) 737-7070

Proposed Plugging Method: Ordered 425 sxs 60/40 pozmix - 4% gel - 500# hulls.
DV Tool at 1457' w/400 sxs.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/25/2010 10:15 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Hooked to 5 1/2" casing - pumped 425 sxs 60/40 pozmix - 4% gel with 500# hulls.
S.I.P. 150#.

Perfs:

Top	Bot	Thru	Comments
3606	3768		OPEN HOLE

12/03/10
2011060243

RECEIVED
KANSAS CORPORATION COMMISSION
JUL 02 2010
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY-TICKET #41638.

Plugged through: CSG

District: 04

Signed

Pat Bedore
(TECHNICIAN)


CM

Form CP-2/3

JUN 30 2010

STEVE MORRISON
 BOX 427
 LOGAN, KS 67646
 CONTR HELBERG DRILLING CO CTY ROOKS
 GEOL FIELD BARRY SE
 E 2039 KB CM 9/15/81 CARD ISSUED 10/8/81 IP SWDW
 ARB OH 3608-3768

7-9-18W
 C E/2 NW NE



API NOT ASSIGNED

	TOPS	DEPTH	DATUM
ANH		1455	+ 584
HEEB		3183	-1144
TOR		3209	-1170
LANS		3223	-1184
CONG		3427	-1388
EST ARB		3520	-1481
OTD		3620	-1581
DDTD		3768	-1729

OLD INFO: OPERATOR WAS B-H-P, #1
 WERNER, SPD NA, SET 8" 200, COMP AS
 D&A 11/24/50, CONTR: NA

NO DST'S

NEW INFO: RE-ENTERED 9/15/81, WSH DWN
 TO OTD, DD 3768 TD, SET 5 1/2" 3608,
 MICT - CO, (ARB OH) AC2500G (20%)
 SWDW - INJ RATE SATISFACTORY

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS