

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-30337-00-01  
Spot: SWSWSE Sec/Twnshp/Rge: 20-15S-17W  
330 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: BOOS A OWWO Well #: 1  
County: ELLIS Total Vertical Depth: 3600 feet

Operator License No.: 33636  
Op Name: TRIUNITED INVESTORS, LLC  
Address: 2149 VIZCAYA CIR  
CAMPBELL, CA 95008

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	1111	0	250 SX
PROD	4.5	3599	0	100 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/21/2010 1:00 PM  
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC  
Proposal Rcvd. from: JOHN FOSE Company: TRIUNITED INVESTORS, LLC Phone: (785) 623-0002

Proposed Plugging Method: Ordered 450 sxs 60/40 pozmix - 4% gel - 500# hulls - 9 sxs gel.  
Perf Tech shot a two hole shot at 550'.  
PBTD 3490'.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 09/21/2010 6:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Professional Pulling Service RIH with tubing to 3390'.  
Allied rigged to tubing and pumped 9 sxs gel - followed with 45 sxs cement with 200# hulls.  
Pulled tubing to 1600' - pumped 95 sxs cement with 200# hulls - cement circulated.  
POOH. Hooked up to casing - pumped 35 sxs cement.  
Max. P.S.I. 700#.  
Hooked up to Braden head - pumped 30 sxs cement.  
Max. P.S.I. 700#.  
Shut both sides.

Perfs:

Remarks: ALLIED CEMENTING COMPANY-TICKET #36834.

Plugged through: TBG

District: 04

Signed

*Ray A. Dinkel*

(TECHNICIAN)

CM

RECEIVED  
SEP 27 2010  
KCC WICHITA

SEP 23 2010