

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-141-20422-00-00
Spot: W2W2NE Sec/Twnshp/Rge: 1-9S-12W
1510 feet from N Section Line, 2200 feet from E Section Line
Lease Name: BRUMMER Well #: 1
County: OSBORNE Total Vertical Depth: 4150 feet

Operator License No.: 5145
Op Name: DREILING OIL INC
Address: 1008 CODY AVE PO BOX 550
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	223		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 02/12/2011 3:00 AM
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING
Proposal Rcvd. from: TOM ALM Company: DREILING OIL INC Phone: (785) 625-8327

Proposed Plugging Method: Ordered 230 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: PAT STAAB Witness Type: NONE
Date/Time Plugging Completed: 02/12/2011 6:00 AM KCC Agent: PAT STAAB

Actual Plugging Report:

1st. Plug at 4068' w/25 sxs.
2nd. Plug at 992' w/25 sxs.
3rd. Plug at 764' w/100 sxs.
4th. Plug at 273' w/40 sxs.
5th. Plug at 40' w/10 sxs.
Rathole with 30 sxs.


Perfs:

Remarks: QUALITY OIL WELL CEMENTING.

Plugged through: DP

District: 04

Signed



(TECHNICIAN)

CM

RECEIVED
FEB 25 2011
KCC WICHITA

Form CP-2/3

FEB 22 2011