

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-00167-00-00
Spot: SWSWSE Sec/Twnshp/Rge: 11-15S-13W
330 feet from S Section Line, 2310 feet from E Section Line
Lease Name: KEJR C Well #: 1
County: RUSSELL Total Vertical Depth: 3296 feet

Operator License No.: 5135
Op Name: FARMER, JOHN O., INC.
Address: 370 W WICHITA AVE PO BOX 352
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	769	0	400 sxs
PROD	4.5	3292	0	200 sxs

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/22/2011 9:00 AM
Plug Co. License No.: 33385 Plug Co. Name: J & M WELL SERVICING, INC.
Proposal Rcvd. from: VAL DREHER Company: FARMER, JOHN O., INC. Phone: (785) 483-8356

Proposed Plugging Method: Ordered 740 sxs 60/40 pozmix - 4% gel - 400# hulls.
Perf: 760'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/22/2011 4:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 3000' - pumped 75 sxs cement with 100# hulls.
Pulled tubing to 2300' - pumped 75 sxs cement.
Pulled tubing to 1550' - pumped 125 sxs cement with 300# hulls.
Pulled tubing to 760' - pumped 70 sxs cement - circulated backside.
POOH. Hooked up to casing and pumped 15 sxs cement at 350# P.S.I.
Hooked on Braden head - pressured up - re-opened casing - cement circulated to casing.
Pumped a total of 155 sxs cement with colored water circulating out Braden head.
Hooked onto Braden head and pumped a total of 225 sxs cement - cement circulated out of the casing.

Perfs:

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #4698.

Plugged through: TBG

District: 04

Signed Ray A. Dinkel
(TECHNICIAN)

CM

RECEIVED
FEB 25 2011
KCC WICHITA

Form CP-2/3

FEB 23 2011