

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-20369-00-00  
Spot: NENENW Sec/Twnshp/Rge: 25-18S-14W  
4950 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: MARK BROWN Well #: 1  
County: BARTON Total Vertical Depth: 3456 feet

Operator License No.: 6988  
Op Name: SMITH, RICHARD E. DBA SMITH OIL O  
Address: 327 W 4TH PO BOX 550  
HUTCHINSON, KS 67501

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3093		
SURF	8.625	241	0	170 SX
PROD	4.5	3453	1623	200 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/27/2011 12:00 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: DALE R. OHL Company: SMITH OIL OPERATIONS Phone: (620) 663-6622

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 500# hulls.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 01/27/2011 4:30 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off perfs and topped with 4 sxs cement.  
Cut casing at 1623'.  
Pulled casing to 1450' - pumped 140 sxs cement with 300# hulls.  
Pulled casing to 860' - pumped 25 sxs cement with 100# hulls.  
Pulled casing to 300' - circulated cement to surface with 165 sxs cement and 100# hulls.  
Pulled casing - hole stayed full.

Perfs:

Top	Bot	Thru	Comments
3022	3027		

Remarks: COPELAND ACID AND CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Bruce Rodie  
(TECHNICIAN)

CM

RECEIVED  
FEB 01 2011

Form CP-2/3

JAN 28 2011

KCC WICHITA