

TO:
STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-003-21462-00-00
Spot: SENWNWNE Sec/Twnshp/Rge: 22-21S-19E
4631 feet from S Section Line, 1988 feet from E Section Line
Lease Name: BENJAMIN Well #: 10
County: ANDERSON Total Vertical Depth: 920 feet

Operator License No.: 33097
Op Name: SOUTHERN STAR CENTRAL GAS PIPE
Address: 4700 HWY 56
OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	6.625	25		NO SXS LISTED
PROD	2.5	892		NO SXS LISTED

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/11/2010 9:00 AM
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.
Proposal Rcvd. from: STEVE BENJAMIN Company: _____ Phone: (785) 448-4804

Proposed Plugging Method: TIE TO 2 1/2"- ESTABLISH FLOW RATE & SQUEEZE CEMENT INTO FORMATION UNTIL DESIRED AMOUNT OF CEMENT AND PRESSURE IS ACHIEVED, FILLING WELL TO SURFACE. CUT OFF PIPE 3 FT. BELOW SURFACE, CUT, CAP AND BACKFILL.

Plugging Proposal Received By: LEVI SHORT WitnessType: PARTIAL
Date/Time Plugging Completed 10/11/2010 10:00 AM KCC Agent: LEVI SHORT

Actual Plugging Report:

RUN 1-INCH PIPE IN 2-INCH PIPE AND PUMP CEMENT FROM TD (920 FEET) TO SURFACE. PULL PIPE THEN HOOK ON TO 2-INCH AND SQUEEZE CEMENT AT 750 PSI. A TOTAL OF 59 SACKS OF CEMENT WERE USED TO PLUG THE WELL.

Perfs:

Top	Bot	Thru	Comments
838	861		

RECEIVED

JAN 14 2011 LS

KCC Chanute Dist #3

Remarks:

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)

RECEIVED

JAN 31 2011

KCC WICHITA ✓

Form CP-2/3