

TO:  
STATE CORPORATION COMMISSIO  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 6720

API Well Number: 15-003-21934-00-00  
Spot: NENENENE Sec/Twnshp/Rge: 22-21S-19E  
5088 feet from S Section Line, 222 feet from E Section Line  
Lease Name: BENJAMIN Well #: 14  
County: ANDERSON Total Vertical Depth: 890 feet

Operator License No.: 33097  
Op Name: SOUTHERN STAR CENTRAL GAS PIPE  
Address: 4700 HWY 56  
OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	6.25	50		NO SXS LISTED
PROD	2.875	860		83 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/20/2010 10:00 AM  
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.  
Proposal Rcvd. from: STEVE BENJAMIN Company: \_\_\_\_\_ Phone: (785) 448-4804

Proposed Plugging Method: TIE TO 2 7/8"- ESTABLISH FLOW RATE & SQUEEZE CEMENT INT O FORMATION UNTIL DESIRED AMOUNT OF CEMENT AND PRESSURE IS ACHIEVED, FILLING WELL TO SURFACE. CUT OFF PIPE 3 FT. BELOW SURFACE, CUT, CAP AND BACKFILL.

Plugging Proposal Received By: LEVI SHORT WitnessType: PARTIAL  
Date/Time Plugging Completed 10/20/2010 11:00 AM KCC Agent: LEVI SHORT

Actual Plugging Report:

RUN 1-INCH PIPE IN 2-INCH PIPE AND PUMP CEMENT FROM TD (890 FEET) TO SURFACE. PULL PIPE THEN HOOK ON TO 2-INCH AND SQUEEZE CEMENT AT 750 PSI. A TOTAL OF 67 SACKS OF CEMENT WERE USED TO PLUG THE WELL.

Perfs:

Top	Bot	Thru	Comments
835	846		
820	831		

RECEIVED

JAN 14 2011 LS

KCC Chanute Dist. #3

Remarks:

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)

RECEIVED  
JAN 31 2011

Form CP-2/3

KCC WICHITA