

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 6568
Name: Kaiser-Francis Oil Company
Address 1: P.O. Box 21468
Address 2: _____
City: Tulsa State: OK Zip: 74121 + 1468
Contact Person: Charlotte VanValkenburg
Phone: (918) 491-4314
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Chase Depth to Top: 2605' Bottom: 2700' T.D. 2750

Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 175-20381-00-00
Spot Description: _____
SE SE NE NW Sec. 14 Twp. 33 S. R. 33 East West
1,250 Feet from North / South Line of Section
2,490 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Seward
Lease Name: French Well #: 1
Date Well Completed: 1/13/79
The plugging proposal was approved on: 3/11/11 (Date)
by: Steve Durrant (KCC District Agent's Name)
Plugging Commenced: 3/11/11
Plugging Completed: 3/14/11

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
Chase	Gas	Surface	8 5/8"	561'	None
		Production	4 1/2"	2745'	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

2 3/8" tbg stuck & previously cut off @ 2230' . 4 1/2" casing parted @ 1120' w/ sand fill above perms & tbg fish @ 1149' . Run tbg @ 1118' & spot 25 sks Class "C" cement . POH & WOC . Tag TOC @ 1108'. Mix & pump additional 20 sks Class "C" cement . POH & WOC weekend . Tag TOC @ 365' . Call KCC for alternative procedure . RU down 8 5/8" surface outlet , mix & pump 120 sks Class "C" cement , leave 8 5/8" full . Run tbg @ 365' , mix & pump 20 sks Class "C" cement & fill 4 1/2" to surface.

Plugging Contractor License #: 33338 Name: Orr Enterprises, Inc.
Address 1: P.O. Box 1706 Address 2: _____
City: Duncan State: Oklahoma Zip: 73534 + 1706
Phone: (580) 467-0258
Name of Party Responsible for Plugging Fees: Kaiser-Francis Oil Company
State of Oklahoma County, Tulsa, ss.
Charlotte Van Valkenburg Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and, the same are true and correct, so help me God.

Signature: C. Van Valkenburg

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Char. or Ver. fac. net

RECEIVED
MAR 25 2011
KCC WICHITA