

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 3293
Name: Russell Oil, Inc.
Address 1: PO Box 8050
Address 2: _____
City: Edmond State: OK Zip: 73083 + _____
Contact Person: LeRoy Holt II
Phone: (405) 752-7600
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

API No. 15 - 193-20788-00-00
Spot Description: _____
NW SW NE NW Sec. 36 Twp. 10 S. R. 34 East West
880 Feet from North / South Line of Section
1,420 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Thomas
Lease Name: Seele D Well #: 1-36
Date Well Completed: 3/19/2011
The plugging proposal was approved on: 3/17/2011 (Date)
by: Pat Staab (KCC District Agent's Name)
Plugging Commenced: 3/19/2011
Plugging Completed: 3/19/2011

Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8 5/8"	268.08'	0'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Plugged well with 220 sacks 60/40 Poz, 4% gel, 1/4# flo-seal per sack. 1st plug @ 2714' with 25 sacks, 2nd plug @ 1712' with 100 sacks, 3rd plug @ 318' with 40 sacks, 4th plug @ 40' to surface iwth 10 sacks, 15 sacks for mouse hole, 30 sacks for rat hole, Consolidated (Ticket #30793). Plug down @ 7:30 pm on 3/19/2011.

Plugging Contractor License #: 33350 Name: Southwind Drilling, Inc.
Address 1: PO Box 276 Address 2: _____
City: Ellinwood State: Kansas Zip: 67526 + _____
Phone: (620) 564-3800
Name of Party Responsible for Plugging Fees: Russell Oil, Inc.

State of Kansas County, Barton, ss.
Jennifer Heape Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Jennifer Heape

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
MAR 24 2011
KCC WICHITA

SOUTHWIND DRILLING, INC.
PLUGGING ORDERS AND REPORTS

Lease: Seele D #1-36

Plugging received from KCC representative:

Name: Pat Staab Date 3-17-11 Time 4:00 PM

1st plug @ 2714 ft. 25 sx. Stands: 43

2nd plug @ 1712 ft. 100 sx. Stands: 27

3rd plug @ 318 ft. 40 sx. Stands: 5

4th plug @ 40 ft. 10 sx. Stands: _____

5th plug @ _____ ft. _____ sx. Stands: _____

Mousehole 15 sx.

Rahole 30 sx.

Total Cement used: 220 sx.

Type of cement 60/40 Poz, 4% Gel, 1/4" F/Seal Per Sack

Plug down @ 7:30 PM 3-19-11

Call KCC When Completed:

Name: Pat Staab Date 3-21-11 Time 9:00 AM
9:00 AM

RECEIVED
MAR 24 2011
KCC WICHITA