

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

WELL PLUGGING RECORD

K.A.R. 82-3-117

Form CP-4
March 2009

Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 33966
Name: Samson Resources Company
Address 1: 2 West Second Street
Address 2: _____
City: Tulsa State: OK Zip: 74103 + 3103
Contact Person: Ellen McElrath
Phone: (918) 591-1697
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Mississippi Depth to Top: 4,994' Bottom: 5,030' T.D. 5,095'
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 033-20027-00-00
Spot Description: _____
C NE-NE Sec. 23 Twp. 31 S. R. 18 East West
660 Feet from North / South Line of Section
660 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Comanche
Lease Name: Betzer Well #: 1-23
Date Well Completed: 08-16-68
The plugging proposal was approved on: 02-17-11 (Date)
by: Eric McClaren (KCC District Agent's Name)
Plugging Commenced: 2-18-2011
Plugging Completed: 2-23-2011

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
<u>Mississippi (36')</u>	<u>Gas</u>	<u>Surface</u>	<u>8 5/8</u>	<u>482'</u>	<u>0</u>
		<u>Production</u>	<u>4 1/2</u>	<u>5,095'</u>	<u>1,842'</u>

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Pumped 40 bbls mud down 4-1/2" csg. TIH with CIBP. Set at 4,913'. Pumped 10 sxs cmt on top. Loaded casing with mud. Shot 4-1/2" csg at 1,842'. TOH. Layed down same TIH with tbg to 1000'. Pumped 15 sxs gel and 50 sxs cement. TOH to 515'. Pumped 50 sxs cmt. TOH to 60'. Pumped 20 sxs cmt. Rigged down rig. Dug out cellar. Cut off wellhead. Topped off 8-5/8" csg with 44 sxs cmt. Welded on ID plate.

Plugging Contractor License #: 33311 Name: Phil Dollar Oilfield Services, Inc
Address 1: P.O. Box 744 Address 2: _____
City: Perryton State: TX Zip: 79070
Phone: (806) 435-3373

Name of Party Responsible for Plugging Fees: Samson Resources Company
State of Oklahoma County, Tulsa, ss.
Ellen McElrath Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God:

Signature: Ellen McElrath

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED

MAR 14 2011

KCC WICHITA