

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

ORIGINAL

Form CP-4
March 2009

Type or Print on this Form

Form must be Signed

All blanks must be Filled

WELL PLUGGING RECORD

K.A.R. 82-3-117

OPERATOR: License #: 5208
 Name: Exxon Mobil Corporation
 Address 1: P.O. Box 4358
 Address 2: _____
 City: Houston State: TX Zip: 77210 + _____
 Contact Person: Richard Redus
 Phone: (281) 654-1656
 Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (If needed attach another sheet)
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 081-00264 -0060
 Spot Description: _____
 _____ NW NW SE Sec. 8 Twp. 28 S. R. 34 East West
2640 2440 Feet from North / South Line of Section
2640 2466 Feet from East / West Line of Section
 Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
 County: Haskell
 Lease Name: Goering Well #: 1
 Date Well Completed: 3/10/2011
 The plugging proposal was approved on: 3/09/2011 (Date)
 by: Steve Durrant (KCC District Agent's Name)
 Plugging Commenced: 3/09/2011
 Plugging Completed: 3/10/2011

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	10 3/4"	550'	None
		Production	7"	2561'	None
		Slotted Liner	5 1/2"	2548' - 2811'	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Pickup 2 3/8" work string & TIH @ 1428' to collapsed casing (Previously milled & swaged with failed results) . Circulate hole w/ 9.5 ppg mud & spot 50 sks Class "C" cement up to 1129' , POH w/ tbg & WOC . Tag TOC @ 1138' . RU wireline trk & pull cement bond log from 1120' to surface & evidence cement to surface . TIH w/ tbg & circulate Class "C" cement to surface inside 7" casing w/ 115 sks . POH w/ tbg , top out 7" & 10 3/4" casing strings w/ 5 sks cement . Dig out & cut off 4' below ground level & weld ID plate.

Plugging Contractor License #: 33338 Name: Orr Enterprises, Inc.
 Address 1: P.O. Box 1706 Address 2: _____
 City: Duncan State: Oklahoma Zip: 73534 + 1706
 Phone: (580) 467-0258
 Name of Party Responsible for Plugging Fees: EXXONMOBIL PROD. CO.
 State of KANSAS County, GRANT ss.
OCTAVIO D. MORALES (Print Name) Employee of Operator or Operator on above-described well.

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct so help me God.

Signature: Octavio D Morales

RECEIVED
MAR 21 2011
KCC WICHITA

✓