

Notice: Fill out COMPLETELY  
and return to Conservation Division at  
the address below within  
60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 34318  
Name: Berexco, L.L.C.  
Address 1: P. O. Box 723  
Address 2: 2020 N Bramblewood, Wichita KS 67201  
City: Hays State: KS Zip: 67601 + \_\_\_\_\_  
Contact Person: Dennis Kirmer  
Phone: ( 785 ) 628-6101  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: E-07,607-0019  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Plattsmouth Depth to Top: 2928 Bottom: 2932 T.D. \_\_\_\_\_  
Toronto Depth to Top: 3000 Bottom: 3005 T.D. \_\_\_\_\_  
L-KC-C Depth to Top: 3083 Bottom: 3093 T.D. \_\_\_\_\_

API No. 15 - 167-08578-0001  
Spot Description: \_\_\_\_\_  
SW 32 NE NW Sec. 16 Twp. 15 S. R. 13  East  West  
4,290 4158 Feet from  North /  South Line of Section  
3,800 3312 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Russell  
Lease Name: Bitter Well #: 4 A  
Date Well Completed: 3/62  
The plugging proposal was approved on: 2-16-11 (Date)  
by: Ray Dinkel (KCC District Agent's Name)  
Plugging Commenced: 2-16-11  
Plugging Completed: 2-16-11

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Production	4 1/2	3275'	

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Run open end tbg to 2955'. Spot 75 SXS 60/40 poz 4% gel and 100# hulls. Pull tbg to 1860'. Spot 55 sxs cement w 100# hulls. Pull tbg to 1060'. Mix 75 sxs cement and circulate good cement to surface. Pull tbg out of hole. Hook up to 4 1/2 csg. Mix 5 sxs cement and pressure to 200#-held. Witnessed by Ray Dinkel. Well Plugged 2:00 p.m.

Plugging Contractor License #: 34318 Name: Berexco, L.L.C.  
Address 1: P. O. Box 723 Address 2: 2020 N Bramblewood, Wichita KS 67201  
City: Hays State: KS Zip: 67601 + \_\_\_\_\_  
Phone: ( 785 ) 628-6101  
Name of Party Responsible for Plugging Fees: Berexco, L.L.C.  
State of Kansas County, Sedgwick, ss.  
Dennis Kirmer  Employee of Operator or  Operator on above-described well,  
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Dennis Kirmer

RECEIVED  
FEB 28 2011  
KCC WICHITA