

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 4058  
Name: American Warrior INC  
Address 1: P.O.Box 399  
Address 2: \_\_\_\_\_  
City: Garden City State: KS Zip: 67846 + \_\_\_\_\_  
Contact Person: Kevin Wiles SR  
Phone: (620) 275-2963 EXT 306  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Arbuckle Depth to Top: 3272 Bottom: 3288 T.D. 3288  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

02243

API No. 15 - 053-29,243-00-003  
Spot Description: NE sec. 2-17s-10w  
C NW NE NE Sec. 2 Twp. 17 S. R. 10  East  West  
4,950 Feet from  North /  South Line of Section  
660 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Ellsworth  
Lease Name: Stratmann Well #: 2  
Date Well Completed: 4-27-1940  
The plugging proposal was approved on: 2-17-11 (Date)  
by: Jeff Klock (KCC District Agent's Name)  
Plugging Commenced: 2-21-11  
Plugging Completed: 2-21-11

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8-5/8	232	None
		Production	7	3272	None
		Liner	4-1/2	3272	

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set CIBP @ 3200' dump 2 sks cement on top, perforate @ 1250', 950', 280' ran 2-3/8" tbg, to 1250' pump 50 sks cement w/ 100#s hulls, pull tbg to 950, pump 50 sks cement, pull tbg, to 280' pump 80 sks cement, circulated cement, pull tbg, hook up to annulus pump 15 sks cement, top off casing w/ 20 sks, Job complete. (cement 60/40 Poz 4% Gel.)

RECEIVED  
MAR 11 2011  
KCC WICHITA

Plugging Contractor License #: 32382 Name: Swift Services INC  
Address 1: P.O.Box 466 Address 2: \_\_\_\_\_  
City: Ness city State: KS Zip: 67560 + 0466  
Phone: (785) 798-2300  
Name of Party Responsible for Plugging Fees: American warrior INC  
State of Kansas County, Ellsworth, ss.  
Kevin Wiles SR  Employee of Operator or  Operator on above-described well,  
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: \_\_\_\_\_