

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 4058
Name: American Warrior INC
Address 1: P.O.Box 399
Address 2: _____
City: Garden City State: KS Zip: 67846 + _____
Contact Person: Kevin Wiles SR
Phone: (620) 275-2963 EXT 306
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Kansas City Depth to Top: 2762 Bottom: 3319 T.D. 3320
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 053-20,685-00=00
Spot Description: SE. sec 5-16s-10w
C N/2, SW, SE Sec. 5 Twp. 16 S. R. 10 East West
1,700 981 Feet from North / South Line of Section
1,980 2193 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Ellsworth
Lease Name: Elsie Oshel Well #: 1
Date Well Completed: 3-26-81
The plugging proposal was approved on: 2-17-11 (Date)
by: Jeff Klock (KCC District Agent's Name)
Plugging Commenced: 2-22-11
Plugging Completed: 2-23-11

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8-5/8	350	None
		Production	4-1/2"	3324	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran 2-3/8" tbg to 2100' cir hole, mix 50 sks 60/40 poz 4% gel spot on bottom. pull tbg, perforate @ 1300', 1000', 400', ran tbg to 1300' pump 35 sks cement w/ 100#s hulls, pull tbg. to 1000' pump 35 sks cement w/ 100#s hulls, pull tbg. to 400' pump. 55 sks cement, circulated cement, pull tbg, hook up to braden head, pump, 50 sks cement, top off 4-1/2" csg, Job Complete

Plugging Contractor License #: 32382 Name: Swift Services INC
Address 1: P.O.Box 466 Address 2: _____
City: Ness city State: KS Zip: 67560 + 0466
Phone: (785) 798-2300
Name of Party Responsible for Plugging Fees: American warrior INC
State of Kansas County, Ellsworth, ss.
Kevin Wiles SR Employee of Operator or Operator on above-described well,
(Print Name)

RECEIVED
MAR 11 2011
KCC WICHITA

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: _____