

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 March 2009 Type or Print on this Form Form must be Signed All blanks must be Filled

OPERATOR: License #: 9408 Name: Trans Pacific Oil Corporation Address 1: 100 S. Main, Suite 200 Address 2: City: Wichita State: KS Zip: 67202 Contact Person: Glenna Lowe Phone: (316) 262-3596 Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic Water Supply Well Other: SWD Permit #: ENHR Permit #: Gas Storage Permit #: Is ACO-1 filed? Yes No If not, is well log attached? Yes No Producing Formation(s): List All (If needed attach another sheet) Depth to Top: Bottom: T.D. Depth to Top: Bottom: T.D. Depth to Top: Bottom: T.D.

API No. 15 - 053-21260-00-00 Spot Description: W2-NE-SE Sec. 35 Twp. 15 S. R. 9 East West 1,980 Feet from North South Line of Section 2,310 Feet from East West Line of Section Footages Calculated from Nearest Outside Section Corner: NE NW SE SW County: Ellsworth Lease Name: Janzen "A" Well #: 1-35 Date Well Completed: 3/6/2011 The plugging proposal was approved on: 2/24/2011 (Date) by: Shane (KCC District Agent's Name) Plugging-Commenced: 3/5/2011 Plugging Completed: 3/6/2011

Show depth and thickness of all water, oil and gas formations.

Table with 6 columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface, Conductor & Production) (Casing, Size, Setting Depth, Pulled Out). Row 1: Surface, 8 5/8", 298', 0'.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Plugged well with 180 sacks, 60/40 Poz, 4% gel. 1st plug @ 3041' with 35 sacks, 2nd plug @ 1000' with 35 sacks, 3rd plug @ 700' with 35 sacks, 4th plug @ 350' with 35 sacks, 5th plug @ 60' to surface with 25 sacks, 15 sacks for rat hole. Plug down @ 9:15 am on 3/6/2011. (Allied Ticket # 038718).

Plugging Contractor License #: 33350 Name: Southwind Drilling, Inc. Address 1: PO Box 276 Address 2: City: Ellinwood State: Kansas Zip: 67526 Phone: (620) 564-3800 Name of Party Responsible for Plugging Fees: Trans Pacific Oil Corporation State of Kansas County: Barton, ss. Jennifer Heape (Print Name) Employee of Operator or Operator on above-described well

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Jennifer Heape

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED MAR 08 2011

KCC WICHITA

SOUTHWIND DRILLING, INC.  
PLUGGING ORDERS AND REPORTS

Lease: JANZEN A 15-053-21260-00-00

Plugging received from KCC representative:

Name: Shane Date 24<sup>th</sup> Feb Time 3:00 p.m

<sup>top Arb</sup>  
1<sup>st</sup> plug @ 3041' ft. 35 sx. Stands: 50

2nd plug @ 1000 ft. 35 sx. Stands: 16

3rd plug @ 700 ft. 35 sx. Stands: 11

<sup>50' below S.P.</sup>  
4th plug @ 350 ft. 35 sx. Stands: 6

5th plug @ 60' to surface ft. 25 sx. Stands: 1

Mousehole        sx.

Rahole 15 sx.

Total Cement used: 180 sx.

Type of cement 60/40 POS 4% Gel

Plug down @ 9:15 AM 3-6-11 by Allied

Call KCC When Completed:

Name: Duane Date 3/7/11 Time 9:50 AM

RECEIVED  
MAR 08 2011  
KCC WICHITA