

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

WELL PLUGGING RECORD

K.A.R. 82-3-117

Form CP-4
March 2009

Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 4706
Name: Messenger Petroleum Inc
Address 1: 525 S Main
Address 2: _____
City: Kingman State: KS Zip: 67068 + _____
Contact Person: Jon F. Messenger
Phone: (620) 532-5400
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Simpson Depth to Top: 4715 Bottom: 4750 T.D. 4750
Mississippian Depth to Top: 4340 Bottom: 4377 T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 095-21140-00-00
Spot Description: _____
SE SE SE NW Sec. 34 Twp. 30 S. R. 7 East West
2,350 Feet from North / South Line of Section.
2,350 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Kingman
Lease Name: Norris C Well #: 1
Date Well Completed: _____
The plugging proposal was approved on: 01-28-2011 (Date)
by: Steve VanGeison/Jeff Klock (KCC District Agent's Name)
Plugging Commenced: 02-03-2011
Plugging Completed: 02-04-2011

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
Simpson	oil & water	surface	8-5/8"	264	none recovered
Miss	oil, gas, & water	production	4-1/2"	4715	2825'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Cut surface casing off below ground. Sanded in well - Tagged sand at 3350' (CIBP had already been set @ 4460' & 3419'). Bailed 4 sacks cement on sand. Ripped casing @ 3040' & 2825'; pipe came free @ 2825'. Pulled casing up to 1300' & pumped 35 sacks cement, 3% CC & 100# hulls. Pulled to 800' & pumped 35 sacks cement, 3% CC & 100# hulls. Pulled to 295' & pumped 110 sacks cement to surface. Pulled rest of casing & topped off well with 25 sacks dry cement. Topped well off with 75 sacks 100# slurry, backfilled cellar.

RECEIVED
MAR 04 2011

Plugging Contractor License #: 31925 Name: Quality Well Service, Inc.
Address 1: 190 US Hwy 56 Address 2: _____
City: Ellinwood State: Kansas Zip: 67526 + _____
Phone: (620) 727-3410

KCC WICHITA

Name of Party Responsible for Plugging Fees: Messenger Petroleum, Inc.
State of Kansas County, Kingman, ss.
Jon F. Messenger Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Jon F. Messenger