

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 32334
Name: Chesapeake Operating, Inc.
Address 1: P.O. Box 18496
Address 2: _____
City: Oklahoma City State: OK Zip: 73154 + 0496
Contact Person: David Wiist
Phone: (405) 935 - 3906
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
Winfield Depth to Top: 2,508' Bottom: 2,518' T.D. 2,937'
Council Grove Depth to Top: 2,694' Bottom: 2,887' T.D. 2,937'
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 075-20120-5000
Spot Description: _____
SW NE NW SE Sec. 25 Twp. 23 S. R. 40 East West
3,300 Feet from North / South Line of Section
1,980 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Hamilton
Lease Name: Cook Well #: 1-25
Date Well Completed: 11/17/1975
The plugging proposal was approved on: 2/25/2011 (Date)
by: Steve Bond (KCC District Agent's Name)
Plugging Commenced: 2/25/2011
Plugging Completed: 2/28/2011

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
Winfield	Gas	Surface	8 5/8"	314'	0'
Council Grove	Gas	Production	4 1/2"	2,934'	0'
Permian	Water				

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

See Attached Plugging activity

RECEIVED
MAR 10 2011

Plugging Contractor License #: 99996 Name: Allied Cementing Co., Inc. **KCC WICHITA**
Address 1: P.O. Box 31 Address 2: _____
City: Russell State: KS Zip: 67665 + _____
Phone: (_____) _____
Name of Party Responsible for Plugging Fees: Chesapeake Operating, Inc.
State of Oklahoma County, Oklahoma, ss. _____
David Wiist Jr. Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God:

Signature: David Wiist
Digitally signed by David Wiist
DN: dc=net, dc=chkenegy, ou=Users and Groups, cn=David Wiist, email=David.Wiist@chic.com
Date: 2011.03.09 07:10:08 -06'00'

Cook 1-25: Daily Activity – P&A

2/25/2011 MIRU SUPERIOR WELL SVC, RIG 5 # HPJSAM RAN IN W/ TBG OPEN ENDED TO 2205' 67 JTS, CWI SDFWE, WILL PLUG ON 2 - 28 - 2011

2/28/2011 HPJSAM RIG CREW FINISHED RUNNING TBG OPEN ENDED TO 2508' MIRU ALLIED CEMENTING CO. PMP DOWN TBG W/ 150 # COTTON SEED HULLS AND 25 SX CMT 2508' TO 2100' PULLED UP TO 2013 AND PMP 150 # COTTON SEED HULLS AND 50 SX CMT FROM 2013' TO 1200' TOH W/ TBG, MIRU LOG - TECH OF KANSAS. RAN CBL FROM 1000' TO 0' TOC @ 614' PERF SQZ SHOT @ 320' RAN TBG BACK TO 1000' SPOT 35 SX CMT PULG FROM 1000' TO 450' HOOK ON TO 4 1/2 CSG AND PMP 100 SX CMT DOWN 4 1/2 CSG AND CMT DID CIRCULATE TO SURFACE. 4 1/2 CSG WAS FULL OF CMT, RDMO. FINAL, KCC REP IS KEN JEHLIK, CUT OFF CSG 4' BELOW GL, WELD ON ID PLATE AND CLEAN UP LOCATION, WELL IS PLUGGED,

RECEIVED

MAR 10 2011

KCC WICHITA

ALLIED CEMENTING CO., LLC. 040885

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT
040885

DATE <u>2-28-11</u>	SEC. <u>25</u>	TWP. <u>22</u>	RANGE <u>40</u>	CALLED OUT	ON LOCATION <u>9:00am</u>	JOB START <u>1:30pm</u>	JOB FINISH <u>2:00pm</u>
LEASE <u>COOK</u>	WELL# <u>125</u>	LOCATION <u>Surface on well</u>		COUNTY <u>Haskell</u>		STATE <u>KS</u>	
(OLD OR NEW (Circle one)) <u>NEW</u>							

CONTRACTOR <u>Sussex</u>		OWNER	
TYPE OF JOB <u>ACF</u>			
HOLE SIZE	T.D.	CEMENT	
CASING SIZE <u>4 1/2</u>	DEPTH <u>2508</u>	AMOUNT ORDERED <u>300 sks 60.40</u>	
TUBING SIZE <u>2 3/8</u>	DEPTH <u>2508</u>	<u>400' huls used 210 sks + 300' huls</u>	
DRILL PIPE	DEPTH	<u>400' huls outside</u>	
TOOL	DEPTH		
PRES. MAX	MINIMUM	COMMON	<u>126 @</u>
MEAS. LINE	SHOE JOINT	POZMIX	<u>24 @</u>
CEMENT LEFT IN CSG.		GEL	<u>@</u>
PERFS.		CHLORIDE	<u>@</u>
DISPLACEMENT		ASC	<u>@</u>

EQUIPMENT

PUMP TRUCK	CEMENTER	<u>Fuzz</u>	
# <u>431</u>	HELPER	<u>Davian</u>	
BULK TRUCK			
# <u>394</u>	DRIVER	<u>Jerry</u>	
BULK TRUCK			
#	DRIVER		
		HANDLING	<u>310</u>
		MILEAGE	<u>105.54</u>

REMARKS:

<u>2508' @ 2508' with 150' huls</u> <u>60 sks @ 2000' with 150' huls</u> <u>35 sks @ 1000'</u> <u>102 sks @ 1000' to surface</u> <u>Case beside</u> Job complete @ <u>12:00</u> THANKS FOR YOUR SERVICE A.T.C. # <u>801852</u>	TOTAL _____ SERVICE _____ DEPTH OF JOB <u>2508</u> PUMP TRUCK CHARGE _____ EXTRA FOOTAGE _____ MILEAGE <u>9.5</u> MANIFOLD _____ TOTAL _____
---	---

CHARGE TO: Cherokee Cressy

STREET _____
CITY _____ STATE _____ ZIP _____

PW # 218358

To Allied Cementing Co., LLC:
You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

PRINTED NAME Dennis Frick TOTAL CHARGES _____
DISCOUNT _____ IF PAID IN 30 DAYS

SIGNATURE Dennis Frick RECEIVED
MAR 10 2011

KCC WICHITA

AFE 801852

LOG-TECH OF KANSAS, INC.

86 SW 10 AVE.
GREAT BEND, KANSAS 67530
(620) 792-2167

INVOICE

6467

Date 2-28-2011

CHARGE TO: Champion Operating
 ADDRESS _____
 R/A SOURCE NO. _____ CUSTOMER ORDER NO. _____
 LEASE AND WELL NO. Capt #125 FIELD _____
 NEAREST TOWN Syr COUNTY Harrison STATE K.S
 SPOT LOCATION 5700 FSI 8196N EFL SEC. 25 TWP. 22S RANGE 16W
 ZERO 10' A.C.I. CASING SIZE 4 1/2 WEIGHT _____
 CUSTOMER'S T.D. _____ LOG TECH _____ FLUID LEVEL Full
 ENGINEER James Grogg OPERATOR Champion Grogg

PERFORATING				
Description	No. Shots	Depth From	To	Amount
OPEN HCC (7125 762)	2	320	721	

DEPTH AND OPERATIONS CHARGES					
Description	Depth From	To	Total No. Ft	Price Per Ft	Amount
Run 1- R/CBL/CCL	0	1000	1000	.21	
" "	1000	10'	10	.29	

MISCELLANEOUS		
Description	Quantity	Amount
Service Charge		

PRICES SUBJECT TO CORRECTION BY BILLING DEPARTMENT

RECEIVED THE ABOVE SERVICES ACCORDING TO THE TERMS AND CONDITIONS SPECIFIED ON THE REVERSE SIDE TO WHICH WE HEREBY AGREE.

x James Grogg 2-28-11
 Customer Signature Date

Sub Total _____
 Code Ref. _____ Tool Insurance _____
 Tax _____

WHITE - Original CANARY - File Copy PINK - Customer Copy GOLDENROD - Field Copy

RECEIVED
 MAR 10 2011
 KCC WICHITA