

Notice: Fill out COMPLETELY
and return to Conservation Division at
the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 5004
Name: Vincent Oil Corporation
Address 1: 155 N. Market, Ste 700
Address 2: _____
City: Wichita State: KS Zip: 67202 + 1821
Contact Person: M.L. Korphage
Phone: (316) 262-3573
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
_____ Depth to Top: _____ Bottom: _____ T.D. 4770
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 055-22087-00-00
Spot Description: ~NE-SE-NW-SW
NE SE NW SW Sec. 28 Twp. 22 S. R. 27 East West
1,660 Feet from North / South Line of Section
1,270 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Finney
Lease Name: Finnup Trust Well #: 1-28
Date Well Completed: 11/16/2010
The plugging proposal was approved on: 11/16/2010 (Date)
by: Jerry Stapleton, KCC District I (KCC District Agent's Name)
Plugging Commenced: 11/16/2010
Plugging Completed: 11/16/2010

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface Casing	8 5/8"	328'	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Filled hole with rotary mud and set cement plugs through drill pipe as follows:
50 sx plug at 1860'; 80 sx plug at 990'; 50 sx plug at 360'; and 20 sx plug at 60' to surface.
Plugged the rathole with 30 sx and the mousehole with 20 sx..
Used a total of 250 sx 60 / 40 POZ (4% Gel & & 1/4# flow-seal/sx)
Cementing by Allied Cementing Co. LLC, (Ticket #036874)
Plug down at 9:30PM 11/16/2010

RECEIVED
MAR 03 2011
KCC WICHITA

Plugging Contractor License #: 4958 Name: Mallard JV Inc.
Address 1: P.O. Box 1009 Address 2: _____
City: McPherson State: Kansas Zip: 67460 + 1009
Phone: (620) 241-4640

Name of Party Responsible for Plugging Fees: Vincent Oil Corporation
State of Kansas County, Sedgwick, ss.
M.L. Korphage Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: M.L. Korphage