

Notice: Fill out COMPLETELY  
and return to Conservation Division at  
the address below within  
60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 30931  
Name: Daystar Petroleum, Inc.  
Address 1: 1321 W 93 N  
Address 2: P.O. Box 360  
City: Valley Center State: KS Zip: 67147 + 9136  
Contact Person: Steve Bodine  
Phone: (620) 792-6702  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15 - 009-25347-00-00  
Spot Description: \_\_\_\_\_  
NE SW NW NE Sec. 8 Twp. 16 S. R. 13  East  West  
730 Feet from  North /  South Line of Section  
2,280 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Barton  
Lease Name: Bitter Well #: 1-8  
Date Well Completed: \_\_\_\_\_  
The plugging proposal was approved on: 02/02/2011 (Date)  
by: Bruce Bayse (KCC District Agent's Name)  
Plugging Commenced: 02/03/2011  
Plugging Completed: 02/04/2011

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8-5/8"	891	0
		Production	5-1/2"	3461	2283.50

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

02/03/11 - Drive to location. Wait for backhoe to dig cellar & move propane tank. Dump sand to 3100'. Load hole - 45 bbls. Rig up. Tag sand w/bailer. Tag @ 3070'. Dump 5 sacks of cement w/bailer. Set casing jacks. Set up to pull 5-1/2" casing. Unpack Braden head. Pull slips out. Pull the stretch - 8-1/4". Clean tools. Shut down for day. Drive back to shop.

02/04/11 - Drive to location. Start/warm up rig & tongs. Help rig up perforators. Shoot 5-1/2" casing off @ 2305'. Pull casing w/jacks until free. Pull 15 jts. Shut down for about an hour while Copeland repaired a hose. Set first plug @ 1650'. Dump 190 sacks of cement & 300 lbs of cotton seed hulls. Pull 19 more jts. Set second plug @ 870'. Dump 25 sacks of cement. Pull 12 more jts. Set third plug @ 350'. Dump 105 sacks. Pull last 9 jts for a total of 55 jts. Top hole off - 10 sacks. Rig down casing jacks. Clean up. Rig down. Drive equipment back to shop.

\*\*Pulled 55 jts of 5-1/2" casing for total of 2283.50' (threads off)

Plugging Contractor License #: 6901 Name: D.S. & W. Well Servicing, Inc.  
Address 1: 1822 24th Street Address 2: \_\_\_\_\_  
City: Great Bend State: Kansas Zip: 67530 + \_\_\_\_\_  
Phone: (620) 793-5838  
Name of Party Responsible for Plugging Fees: Daystar Petroleum, Inc.  
State of Kansas County, Barton, ss.  
Steve Bodine  Employee of Operator or  Operator on above-described well,  
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Steve Bodine

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED  
FEB 22 2011  
KCC WICHITA