

Notice: Fill out COMPLETELY
and return to Conservation Division at
the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 34318
Name: Berexco, L.L.C.
Address 1: P. O. Box 723
Address 2: 2020 N Bramblewood, Wichita KS 67201
City: Hays State: KS Zip: 67601 + _____
Contact Person: Curtis Gabel
Phone: (785) 628-6101
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Arbuckle Depth to Top: 3558 Bottom: 3588 T.D. 3588
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 051-30186-0000
Spot Description: _____
NW N2 - NE NE Sec. 9 Twp. 14 S. R. 17 East West
4620 4963 Feet from North / South Line of Section
690 770 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Ellis
Lease Name: Saturin Well #: 2
Date Well Completed: 9-11-65
The plugging proposal was approved on: 2-7-11 (Date)
by: Pat Staab (KCC District Agent's Name)
Plugging Commenced: 2-17-11
Plugging Completed: 2-17-11

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
Arbuckle	Oil/Water	Surface	8 5/8	176'	
		Production	4 1/2	3588'	

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Run open end tubing to 3400'. Rig up Allied Cementing. Spot 8 sxs gel followed by 45 sx 60/40 poz 4% gel 1/4# flothead per sack and 200# hulls.
Pull tbq to 1650'. spot 55 sx cement and 100# hulls.
Pull tbq to 845'. Circulate cement to surface with 65 sxs cement and 100# hulls.
Pull tbq out of hole. Top off 4 1/2 x 8 5/8 annulus. Mix 5 sxs cement. Pressure to 200#, held. Witnessed by Pat Staab. Well plugged 2:45 p.m.

Plugging Contractor License #: 34318 Name: Berexco, L.L.C.
Address 1: P. O. Box 723 Address 2: 2020 N Bramblewood, Wichita KS 67201
City: Hays State: KS Zip: 67601 + _____
Phone: (785) 628-6101
Name of Party Responsible for Plugging Fees: Berexco, L.L.C.
State of Kansas County, Sedgwick, ss.
Curtis Gabel Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Dennis Kimes Pat Staab

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
FEB 28 2011
KCC WICHITA ✓