

Notice: Fill out COMPLETELY
and return to Conservation Division at
the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 5030
Name: Vess Oil Corporation
Address 1: 1700 Waterfront Parkway
Address 2: _____
City: Wichita State: KS Zip: 67206 + 6619
Contact Person: Casey Coats
Phone: (316) 682-1537 ext 104
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: D18381.0
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 185-205⁵33-00-01
Spot Description: NW NW SE NE
NW SE NE Sec. 7 Twp. 23 S. R. 11 East West
3660 Feet from North / South Line of Section
1620 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Stafford
Lease Name: Minnis Well #: 2
Date Well Completed: _____
The plugging proposal was approved on: _____ (Date)
by: Richard Lacey (KCC District Agent's Name)
Plugging Commenced: 1-28-11
Plugging Completed: 2-4-11

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
			8-5/8"	286'	None
			4-1.2"	3694'	900'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran in 3600' of 2" tubing, pumped bottom plug with 50 sacks cement, layed down tubing. Cut casing loose @900'. layed down 4-1/2" casing. Ran in 600' of 2" tubing, pumped 10 sacks gel and 50 sacks cement @600'. pulled tubing up to 300', pumped 50 sacks cement, pulled up to 60' and circulated 30 sacks cement to surface. Plugging Complete

Plugging Contractor License #: 31529 Name: Mike's Testing & Salvage, Inc.
Address 1: P.O. Box 467 Address 2: 1125 S. Main
City: Chase State: Kansas Zip: 67534 + 0467
Phone: (620) 938-2943
Name of Party Responsible for Plugging Fees: Vess Oil Corporation
State of Kansas County, Rice, ss.
Mike Kelso Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Mike Kelso

RECEIVED

MAR 23 2011

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

KCC WICHITA