

KCC OIL/GAS REGULATORY OFFICES

Date: 03/18/11

District: 01

Case #: _____

- New Situation
- Response to Request
- Follow-Up

- Lease Inspection
- Complaint
- Field Report

Operator License No: 4767
 Op Name: Ritchie Exploration, Inc.
 Address 1: 8100 E. 22nd St. N #700
 Address 2: Box 783188
 City: Wichita
 State: Kansas Zip Code: 67278 -3188
 Operator Phone #: (316) 691-9500

API Well Number: 15-057-20,719 -0000
 Spot: SW NE Sec 9 Twp 28 S Rng 22 E / W
 2690 Feet from N / S Line of Section
 2130 Feet from E / W Line of Section
 GPS: Lat: 37.62374 Long: 99.72929 Date: _____
 Lease Name: Maupin-Fisher Well #: 1
 County: Ford

Reason for Investigation:

Request to witness Alternate II completion

Problem:

None: Cement circulated to surface and stayed.

Persons Contacted:

Gary Rowe with Ritchie Exploration, Inc.

Findings:

TD @ 5,208
 8 5/8" surface casing set at 343' w/225 sxs cmt. 1" with 200sxs cmt to surface.
 4 1/2" production casing set at 5,204' w/200 sxs cmt.
 Port Collar @ 1,390', cemented with 230 sxs 60/40 pozmix 6% gel with 1/4# Flo-Seal and 300# hulls with cement to the pit. Cement by Allied Cementing
 H2 Plains unit over the hole.

Action/Recommendations:

Follow Up Required Yes No

Date: _____

None required. Alternate II requirements have been met. Cement circulated to the surface and stayed.

Verification Sources:

Photos Taken: _____

- RBDMS
- T-I Database
- Other: _____
- KGS
- District Files
- TA Program
- Courthouse

By: Jerry W. Stapleton

PIRT II

RECEIVED

MAR 28 2011

Form: 02/22/2008

KCC WICHITA

Retain 1 Copy District Office
Send 1 Copy to Conservation Division

RECEIVED

MAR 21 2011

KCC DODGE CITY