

15-051-06245-0000

SHELL PETRO.CORP.
J. L. Rumsey No. 8.

SEC. 23 T. 11 R. 17W
SE SW NW
330' fr SL 983' fr WL NW $\frac{1}{4}$

Total Depth. 3367'
Comm. 8-7-38 Comp. 8-28-38
Shot or Treated. 2000 Gals.
Contractor. Corbett & Barbour
Issued. 11-19-38

County. Ellis



Elevation.

Production. Pot. 3374 B.
No wtr.

CASING:
16 " 135'
10 $\frac{3}{4}$ " 1095'
7 " 3348'

Figures Indicate Bottom of Formations.

sand & gravel	60	600' oil in hole at 3349 5:30 P.M.
sand & shale	136	2200' oil in hole at 3352 6:45 P.M.
shale & shells	445	2900' oil in hole at 3352 7:45 P.M.
red rock	462	3100' oil in hole at 3359
sand	550	
iron	556	
sand & shells	580	
iron	588	
sand	740	
red rock	910	
red rock & iron	1050	
red rock	1060	
shale & shells	1080	
anhydrite	1120	
red bed	1200	
red bed & shells	1375	
shale & shells	1440	
salt	1615	
shale & shells	1965	
lime	2029	
brkn lime	2225	
sdv shale	2240	
brkn lime	2343	
lime shells & shale	2375	
lime	2480	
brkn lime	2530	
shale & shells	2632	
shale	2725	
shale & shells	2785	
brkn lime	2805	
brkn lime	2846	
lime	2952	
brkn lime	3003	
lime good oil stain	3158	
& spots fair porosity		
lime	3199	
brkn lime	3204	
lime trace oil stain	3282	
brkn lime	3309	
conglomerate	3323	
dolomite	3329	
very sm amt por-no oil stain		
shale	3342	
sand fair por & oil		
stain	3344	
shale	3347	
dolomite	3349	
3351 equals 3349 SLCorr.		
dolomite	3367	
Total Depth.		

*Rec'd
9-2-38*