

15-051-02721-00-00

Form PO-214 Sheet 2 (12-47) 20M

LOG OF WELL

SHEET No. 2

District Kansas

Owner The Texas Co.

Farm F.A. Schmidt

Well No. 2

FORMATION		AMOUNT	COLOR	HARD OR SOFT	DEPTH CORES TAKEN	REMARKS
Surface Clay		40				CASING RECORD: Set 8-5/8" csg at 1253' with 600 sacks Lone Star Bulk Cement
Sand	190	150		KB-BM 6.61'		
Shale & Shells	552	362		KB-GL 4.75'		Set 5-1/2" csg at 3576' with 100 sacks Lone Star Cement
Sand	650	98		4 Conroliners		
Shale	710	140		23 Scratchers		
Sand	850	60				
Shale & Shells	1100	250				
Red Bed	1243	143				
Anhydrite	1254	11				
Lime	1275	21				ELEVATION:
Shale & Shells	1760	485				2013 KB
Salt	1860	100				2011 DF
Shale	1905	45				2008 GL
Shale & Lime	2070	165				TOPS:
Lime	2535	465				Anhydrite.....1243'
Shale & Lime	2645	110				Heebner.....3282'
Lime & Shale	2725	80				Lansing.....3328'
Shale & Lime	2815	90				Arbuckle.....3576'
Lime & Shale	2900	85				
Lime	3578 1/2	678 1/2				
TOTAL DEPTH	3578-1/2'					

RECEIVED
STATE CORPORATION COMMISSION

MAY 09 1983

CONSERVATION DIVISION
Wichita, Kansas