

4-042013

5-10

051-02820-00-00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15- - 11-52

^{KCC}
SW NW ~~NE~~ NW /4 SEC. 01, 13 S, 18 W
4290 feet from S section line
~~2310~~ 4950 feet from E section line

Operator license# 32158

Lease: Crissman Well # A-3

Operator: H&B Petroleum Corporation

County: Ellis 117.59

Address: P.O. Box 277
Ellinwood, Kansas 67526

Well total depth 3618 feet
Conductor Pipe: 0 inch @ 0 feet
Surface Pipe: 8 5/8 Inch 200 Feet
W/125 sxs.cmt.

Aband. oil well , Gas well _____, Input well _____, SWD _____, D & A _____

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 8:00 A.M. Day: 10 Month: May Year 1999

Plugging proposal received from: Al Hammerschmidt

Company: H&B Petroleum Corporation Phone: -

Were: Ordered 350 sxs 60/40 pozmix - 10% gel plus 500# hulls.

5 1/2" casing set at 3587' w/125 sxs cement.

Perfs at 3256' - 3262'.

Squeeze at 890' w/150 sxs to 1215'.

Holes in casing at 300' - 1390' - 2650'.

Plugging Proposal Received by: Dennis Hamel

Plugging operations attended by agent? All[], Part[X], None[]

Completed: Hour: 12:30 P.M. Day: 10, Month: May Year: 1999

Actual plugging report: R.I.H. with tubing to 3100'. Spotted 80 sxs cement with 350# hulls.
Pulled tubing to 2100'. Spotted 80 sxs cement with 150# hulls. Pulled tubing to 1100'.
Spotted 90 sxs cement to circulate at surface. POOH with tubing, squeezed casing with 60 sxs
cement. Max. P.S.I. 600#. S.I.P. 500#. R.U. Cementers to 8 5/8" S.P. Squeezed 5 sxs
cement down annulus. Max. P.S.I. 500#. S.I.P. 500#.

Remarks:

Condition of casing(in hole): GOOD ___ BAD ___ Any plug: YES NO ___

Bottom plug(in place): YES ___ CALC ___ NO ___ Dakota plug: YES NO ___

Plugged through TUBING ___ CASING ___ Elevation: G.L.

I did[X] / did not[] observe the plugging.

Dennis L. Hamel
(agent)

Form CP-2/3

INVOICED

DATE MAY 19 1999

INV. NO. 60950

RCND
05-19-99

7102