

6080004

API NUMBER 15- 051-01,021-00-01

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

SE SW SW, SEC. 1, T. 13 S, R. 18 W XX  
330 feet from SE XX section line  
4290 feet from SE XX section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5114  
Operator: National Development  
Name & Address: 205 East Central  
Wichita, Ks. 67202

Lease Name Crissman "C" Well #1 or 2A  
County Ellis 109.53  
Well Total Depth 3370 feet  
Conductor Pipe: Size 0 feet  
Surface Casing: Size 8 5/8 feet 205

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A XX

Other well as hereinafter indicated Re-entry to satisfy area fo influence

Plugging Contractor Production Drilling, Inc. License Number 5386  
Address Hays, Ks.

Company to plug at: Hour: 10:40 AM Day: 7 Month: November Year: 19 84

Plugging proposal received from Wayne Merchant

(company name) National Development (phone) (316) 267-1331

were: Plug with cement

Plugging Proposal Received by Don Dutcher  
(TECHNICIAN)

Plugging Operations attended by Agent?: All XX Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: Noon Day: 7 Month: November Year: 19 84

ACTUAL PLUGGING REPORT Ordered 300 sks common 4% gel. Spotted through tubing at 770 feet opposite a six foot shale in the Cheyenne sandstone. Pumped in 100 sks pulled 10 jts tubing to 470' pumped in 100 sks, pulled 10 jts tubing to 170 feet, pumped in 90 sks cement circulated, laid down tubing and filled hole with 5 sks cement settled to 30 feet. Job complete.

Remarks: Cemented by Allied  
(If additional description is necessary, use BACK of this form)  
NOV 21 1984  
11-26-84  
CONSERVATION DIVISION  
Wichita, Kansas

(I did not observe this plugging.)

Signed Don Dutcher  
(TECHNICIAN)

DATE 12-4-84  
INV. NO. 5763 11-7

DEC 07 1984

JAN 22 1985 MAY 23 1985

FORM CP-2/3  
Rev. 01-84

10  
11-21-84