

4-110056

11-23

API Number: 15-051-02, 819-00-00

TO: ☒ STATE CORPORATION COMMISSION  
 CONSERVATION DIVISION - PLUGGING  
 130 SOUTH MARKET, SUITE 2078  
 WICHITA, KANSAS 67202

NE SW NW /4 SEC. 01, 13 S, 18 W  
 3630 feet from S section line  
 4290 feet from E section line

Operator license# 32158

Lease: Crissman Well # A-2

Operator: H&amp;B Petroleum Corporation

County: Ellis 117.20

Address: P.O. Box 536  
 Clearwater, Kansas 67026

Well total depth 3606 feet  
 Conductor Pipe: 0 inch @ 0 feet  
 Surface pipe 8 5/8 Inch @ 330 feet

Aband. oil well ☒, Gas well ☐, Input well ☐, SWD ☐, D & A ☐

Plugging contractor: Cheyenne Well Service License# 6454

Address: 118 N. Penn - P.O. Box 384 - Ness City, Kansas 67560

Company to plug at: Hour: 11:00 A.M. Day: 23 Month: November Year: 1998

Plugging proposal received from: Al Hammersmith

Company: H&amp;B Petroleum Corporation Phone: 316-564-3002

Were: According to KCC Rules &amp; Regulations.

Ordered 250 sxs 60/40 pozmix - 10% gel - 500# hulls - 14 sxs gel  
 Plug with tubing.

CONSERVATION DIVISION  
WICHITA, KANSAS

STATE CORPORATION COMMISSION

DEC 1 - 1998

12-01-98

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All ☒, Part ☐, None ☐

Completed: Hour: 5:00 P.M., Day: 23, Month: November, Year: 1998

Actual plugging report: 8 5/8" set at 330' w/125 sxs cement. 5 1/2' casing at 3591' w/125 sxs cement. Squeezed October 56 at 683' - 832' w/210 sxs cement.

Ran tubing to 3420' and pumped 14 sxs gel with 150 hulls. Pumped 30 sxs cement with 250# hulls. Pulled to 1860' and pumped 140 sxs with 100# hulls. Pulled all tubing and topped off with 35 sxs cement to Max. P.S.I. 800#. S.I.P. 500#.

Annulus pumped 40 sxs cement to Max. P.S.I. 150#. S.I.P. 150#.

Total 14 sxs gel, 205 sxs cement with 500# hulls.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD BAD Anhy.plugin: YES ☒ NOBottom plug(in place): YES ☒, CALC ☐, NO Dakota plug: YES ☒, NOPlugged through TUBING ☒, CASING ☐ Elevation: 2053 GLI did ☒ / did not ☐ observe the plugging.

Roger L. Moses  
 (agent)

Form CP-2/3

DEC 04 1998

60406

ALPINE OIL &amp; ROYALTY

#2

CRISSMAN

1-13-18W 34  
NE SW NW

Contr. QUAKER DRILLING COMPANY

ELLIS

County

E 2058 RB Comm.

Comp.

8-1-52

IP

90 BOPD

PHY POT

Tops	Depth	Datum
ANH	1289	769
HEEB	3284	-1226
LANS	3336	-1278
CONG	3564	-1506
SIMP	3580	-1522
ARB	3588	-1530
TD	3606	-1548


Casing

8" 330

5" 3591

ACID 500

POLI FKA POOL

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS