

6 062467

API NUMBER 15- 8-7 051-20868-0000 185P

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
209 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW, SEC. 15, T 13 S, R 18 (W)E
4950 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5184

Lease Name Braun Well # 1

Operator: Shields Oil Producers, Inc.

County Ellis 121.87

Name & Address Shields Building

Well Total Depth 3750' feet

Russell, Kansas 67665

Conductor Pipe: Size _____ feet

913-483-3141

Surface Casing: Size 8 5/8 feet 279'

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Rockhold Engineering, Inc. License Number 5111

Address Box 698, Great Bend, Kansas 67530

Company to plug at: Hour: 9:00A.M. Day: 7 Month: August Year: 19 91

Plugging proposal received from Marvin Ratts

(company name) Shields Oil Producers, Inc. (phone) 913-483-3141

were: Order 250 sks. of 60/40 posnix - 8% gel. - 5 sks. hulls.

Plugging Proposal Received by Gilbert G. Scheck (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:00 P.M. Day: 7 Month: August Year: 19 91

ACTUAL PLUGGING REPORT 8 5/8" set at 279' w/150 sks. 5 1/2" set at 3543' w/75 sks.

Top perf. at 3484'. Plugged bottom with sand and 5 sks. cement to 3425'.

Shot pipe 5 times and recovered 600'. Pumped in 5 1/2" casing and circulated

cement from 600' to surface. Pulled all casing and squeezed to 600 P.S.I.

Used 250 sks. cement.

RECEIVED STATE CORPORATION COMMISSION

OCT 01 1991

Remarks: By Allied. Ran Line to 3000'. (If additional description is necessary, use BACK of this form.)

Observe this plugging.

DATE 10-4-91

Signed [Signature] (TECHNICIAN) E.A.D.

INV. NO. 33252