

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-051-20,915 (8-7) (0000) (-0-17, 196) 181
NE NW, SEC. 15, T 13 S, R 18 W

TECHNICIAN'S PLUGGING REPORT

Operator License # 5184

Operator: Shields Oil Producers, Inc.
Name & Address: Shields Building
Russell, Kansas 67665

4950 feet from S section line

4290 feet from E section line

Lease Name Braun Well # 2

County Ellis 125.93

Well Total Depth 3875' feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 265'

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Shields Oil Producers, Inc. License Number 5184

Address Shields Building, Russell, Kansas 67665

Company to plug at: Hour: 9:00A.M. Day: 7 Month: August Year: 19 91

Plugging proposal received from Marvin Ratts

(company name) Shields Oil Producers, Inc. (phone) 913-483-3141

were: Order 50 sks. common, followed w/300 sks. 60/40 posmix - 8% gel. - 15 sks. hulls.

D.V. from 1415' to surface w/175 sks. cement.

Plugging Proposal Received by Gilbert G. Scheck (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:30A.M. Day: 7 Month: August Year: 19 91

ACTUAL PLUGGING REPORT 8 5/8" set at 265' w/150 sks. 5 1/2" set at 3770' w/100 sks.

Open hole at 3770'. Pumped in 5 1/2" 50 sks. common, followed w/150 sks. of

60/40 posmix-8% gel, followed w/5 sks. hulls in 150 sks. cement w/700 P.S.I.

RECEIVED STATE CORPORATION COMMISSION

AUG 21 1991

Remarks: By: Allied Ran Line to 3000'. (If additional description is necessary, use BACK of this form.)

INVOICED (I did not observe this plugging.)

DATE SEP 06 1991

Signed Gilbert G. Scheck (TECHNICIAN) e.a.x

INV. NO. 32984