

To: 1 090793
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

3-25 API NUMBER 15- 097-21,422 0000
E/2 NW SE, SEC. 28, T 29 S, R 17 W/EX
1980 feet from S section line
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License / 4243
Operator: Cross Bar Petroleum, Inc.
Name & Address: 151 N. Main, Ste. 630
Wichita, KS 67202

Lease Name Jantz Well # 2-28
County Kiowa 162.50
Well Total Depth 5000 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 469

Abandoned Oil Well Gas Well Input Well SWD Well D&A **ANS**
Other well as hereinafter indicated

Plugging Contractor Pratt Well Service, Inc. License Number 5893
Address P.O. Box 847, Pratt, KS 67124-0847

Company to plug at: Hour: 2:30 p.m. Day: 25 Month: 3 Year: 1997
Plugging proposal received from Tom Larson
(company name) Larson Engineering (phone) 316-653-7368

were: 5 1/2" at 3189' w/105 sx cement, PBSD 3122', Perfs at 2782-90', Anhydrite 1085', TOC 2325'
1st plug set CIBP at 2753' and dump 2 sx cement on top,
2nd plug at 1085' with 50 sx cement,
3rd plug at 500' with 50 sx cement,
4th plug at 40' with 10 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None
Operations Completed: Hour: 8:10 p.m. Day: 25 Month: 3 Year: 1997

ACTUAL PLUGGING REPORT 1st plug set CIBP at 2753' with 2 sx cement on top;
2nd plug pulled to 1086' and spotted 8 sx gel and 50 sx cement and 7 sx gel,
3rd plug pulled to 505' and spotted 50 sx cement,
4th plug pulled to 40' and spotted 25 sx cement.


RECEIVED
KANSAS CORP COM
1977 MAR 27 A 11:32
03-27-97

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2038' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

~~XXXX~~ did not observe this plugging.

DATE 3-27-97

INVOICE NO. 47830

Signed  (TECHNICIAN)

3-25 MAY 21 1997