

1431378

To: STATE CORPORATION COMMISSION  
Wichita State Office Bldg. PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15-097-21,398 0090  
250' N of  
SW NE NW, SEC. 21, T 29 S, R 17 W/E  
740 feet from NXX section line  
1650 feet from WXX section line

12-30

TECHNICIAN'S PLUGGING REPORT

Operator License # 4243  
Operator: Cross Bar Petroleum, Inc.  
Name & Address: 151 N. Main, Ste. 630  
Wichita, KS 67202

Lease Name Jantz Well # 1-21  
County Kiowa 114.08  
Well Total Depth 3510 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 436

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A  X  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Eagle Drilling, Inc. License Number 5059  
Address: P.O. Box 846, Pratt, KS 67124

Company to plug at: Hour: 7 p.m. Day: 30 Month: 12 Year: 19 95

Plugging proposal received from Butch Steinert  
(company name) Eagle Drilling, Inc. (phone) 316-672-6639

work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1000-20'  
1st plug at 1020' with 50-sx cement, 2nd plug at 460' with 50-sx cement,  
3rd plug at 40' with 10 sx cement,  
4th plug to circulate rathole with 15 sx cement,  
5th plug to circulate mousehole with 10 sx cement.

STATE RECORD  
JAN 05 1996 01-05-96

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None  X

Operations Completed: Hour: 9 p.m. Day: 30 Month: 12 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug at 1020' with 50 sx cement,  
2nd plug at 460' with 50 sx cement,  
3rd plug at 40' with 10 sx cement,  
4th plug to circulate rathole with 15 sx cement.  
5th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.  
(If additional description is necessary, use BACK of this form.)

INVOICED (XXXX) (do not) observe this plugging.

Signed Steve Durrant (TECHNICIAN)

DATE JAN 12 1996

INV. NO. 44550

12-30

FOR KCC USE:

FORM C-1 7/91

FORM MUST BE TYPED

FORM MUST BE SIGNED

ALL BLANKS MUST BE FILLED

EFFECTIVE DATE: 10-18-95

State of Kansas

15-097-21,398-0000

DISTRICT # 1

NOTICE OF INTENTION TO DRILL

Must be approved by the K.C.C. five (5) days prior to commencing well.

SGA? Yes No

Expected Spud Date 12 05 95 month day year

Spot SW NE NW Sec 21 Twp 29S Rg 17 West East

OPERATOR: License # 4243 Name: CROSS BAR PETROLEUM, INC. Address: 151 N. MAIN, SUITE 630 City/State/Zip: WICHITA, KS 67202 Contact Person: C. K. "KEN" MORRISON Phone: 316-265-2279

330 feet from South /North Line of Section 1650 feet from East /West Line of Section IS SECTION x REGULAR IRREGULAR?

(NOTE: Locate well on the Section Plat on Reverse Side)

CONTRACTOR: License #: 5059 Name: EAGLE DRILLING, INC.

County: KIOWA

Lease Name: JANTZ Well #: 1-21

Field Name: WILDCAT

Is this a Prorated/Spaced Field? yes X no

Target Formation(s): COTTONWOOD

Nearest lease or unit boundary: 990'

Ground Surface Elevation: EST. 2075.7 feet MSL

Water well within one-quarter mile: yes X no

Public water supply well within one mile: yes X no

Depth to bottom of fresh water: 180'

Depth to bottom of usable water: 200'

Surface Pipe by Alternate: X 1 2

Length of Surface Pipe Planned to be set: 425'

Length of Conductor pipe required: NONE

Projected Total Depth: 3600'

Formation at Total Depth: BASE EMPORIA

Water Source for Drilling Operations: well farm pond X other

Well Drilled For: Well Class: Type Equipment: X Oil Enh Rec Infield X Mud Rotary X Gas Storage Pool Ext Air Rotary OWWO Disposal X Wildcat Cable Seismic; # of Holes Other

If OWWO: old well information as follows:

Operator: Well Name: Comp. Date: Old Total Depth

Directional, Deviated or Horizontal wellbore? yes X no

If yes, true vertical depth:

Bottom Hole Location:

Exp. 4/13/96

AFFIDAVIT

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will be completed in accordance with the provisions of the act, et. seq.

220' Alt. I Req.

STATE COMMISSION RECEIVED JAN 05 1996

Pusher Butch Stienert SPUD DATE 12-24-95 INIT. RL LENGTH SURFACE PLANNED 425' of 8 3/4" RESERVE PIT STATUS- REMOVE FLUID LINED after salt sect. bbls. when done bbls. RATHOLED AHEAD? Y N SIZE HOLE SURFACE PIPE 8 3/4" @ 436 CONDUCTOR ANHYDRITE T-1000 B-1020 ELEVATION TD 3510 FORMATION Catherwood RAN PIPE @ DV TOOL ALT II DONE SX Y N Arbuckle Plug @ Ft. W/ SX Hug./Council @ Ft. W/ SX Anhydrite Base @ 1020 Ft. W/ 50 SX 1/2 Base Anhy. @ Ft. W/ SX 1/2, 1/2 Plug @ Ft. W/ SX Bottom Surface @ 460 Ft. W/ 50 SX 40' Plug @ 40 Ft. W/ 10 SX RAT HOLE CIRC/W 19 SX MOUSE HOLE W/ 10 SX WATER WELL SX (Irr. Well Pond Hauling) TECHNICIAN S.P DATE 12-30-95 TYPE OF CEMENT 60/40 6% STARTING TIME 7:00 (AM/PM) DATE 12-30-95 COMPLETION TIME 9:00 (AM/PM) DATE 12-30-95 CEMENT COMPANY Halliburton