


WELL PLUGGING RECORD

Get All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

..... County. Sec. 15 Twp. 13 Rge. (E) 20 (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW, SW, SE
Lease Owner JONES, SHELBURNE & FARMER, INC.
Lease Name NIERNBERGER Well No. 1
Office Address RUSSELL, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed 1/13/50 19
Application for plugging filed 1/13/50 19
Application for plugging approved 1/13/50 19
Plugging commenced 1/13/50 19
Plugging completed 1/13/50 19
Reason for abandonment of well or producing formation.....

DRY

If a producing well is abandoned, date of last production NEVER PRODUCED 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well MR. ELDON PETTY
Producing formation NONE Depth to top..... Bottom..... Total Depth of Well 3918 $\frac{1}{2}$ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
	<u>Cemented with 120 sacks.</u>			<u>8 5/8"</u>	<u>188'</u>	<u>None</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet to.....feet for each plug set.

- Hole filled with heavy mud.
- Halliburton plug spotted at 195'.
- Fifteen sacks cement mixed and spotted on top of plug.
- Hole filled to within 20 feet of top with heavy mud.
- Halliburton plug spotted at 20 feet.
- Fifteen sacks cement mixed and hole filled to top with same.

01-18-1950

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to JONES, SHELBURNE & FARMER, INC.
Address RUSSELL, KANSAS

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
John O. Farmer (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me, God.

(Signature) John O. Farmer
RUSSELL, KANSAS
(Address)

SUBSCRIBED AND SWORN to before me this 13 day of January, 1950.

Phyllis Bethany
Notary Public.

My commission expires June 3, 1953

22-7877-S 4-49-10M

PLUGGING
FILE SEC 15T13R20W
BOOK PAGE 124 LINE 10

Jones, Shelburne & Farmer, Inc.

Russell, Kansas

15-051-00512-00-00

CONTRACTOR'S VERIFIED LOG

Operator **JONES, SHELBURNE & FARMER, INC** Farm Name **NIERNBERGER** Well No. **1**

Location **SW SW SE SECTION 15-13-20W**

Pool Name _____ County **ELLIS** State **KANSAS**

Commencement Date **January 2, 1950** Completion Date **January 13, 1950**

Log of Well

Depth		Formation	Deviation from vertical (degrees)	Remarks
From	To			
0	1020	Shale and Shells		
1020	1125	Sand		
1125	1250	Shale		
1250	1550	Red Beds		
1550	1590	Anhydrite		
1590	1930	Shale and Shells		
1930	2050	Shale and Salt		
2050	2100	Shale and Shells		
2100	3560	Lime and Shale		
3560	3860	Lime		
3860	3881	Cherty Conglomerate		
3881	3918 1/2	Lime		
	3918 1/2	Total Depth		

TOPS:

- 1550 Anhydrite
- 3466 Heebner
- 3481 Toronto
- 3508 Kansas City Top
- 3758 Kansas City Base
- 3850 Conglomerate
- 3881 Arbuckle

DRY AND ABANDONED

JAN 18 1950
 COUNTY OF ELLIS
 KANSAS
 01-18-1950

PLUGGING
 FILE - SEC-15-13-20W
 BOOK PAGE 134 OF 10

