

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

Ellis County, Sec. 15 Twp. 13S Rge. (E) 20 (W)

Location as "NE/CNWxSWx" or footage from lines E/2 SW/4 NE/4

Lease Owner Clinton Oil Company

Lease Name Wegele Well No. 1-V

Office Address 6810 West Highway 54, Wichita, Kansas 67209

Character of Well (completed as Oil, Gas or Dry Hole) Dry

Date well completed November 15 1967

Application for plugging filed November 16 1967

Application for plugging approved November 17 1967

Plugging commenced 8 a.m. November 16 1967

Plugging completed 11:00 a.m. November 16 1967

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey, Hays, Kansas

Producing formation Depth to top Bottom Total Depth of Well 3869' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE   | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
|           |         |      |    | 8 5/8" | 251'   | None       |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole w/mud to 720'. Ran 100 sx cement thru drillpipe, mud to 240', plug, 25 sx cement, mud to 40', 10 sx to base of cellar.

Job complete @ 11:00 a.m. November 16, 1967.

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 17 1967  
11-17-1967  
CONSERVATION DIVISION  
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Garvey Drilling Company

Address R. R. 2, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

H. Marvin Douglass (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) H. Marvin Douglass  
H. Marvin Douglass, Clinton Oil Company  
6810 West Highway 54, Wichita, Kansas 67209  
(Address)

SUBSCRIBED AND SWORN to before me this 16th day of November, 1967

January 24, 1968

Allen T. Denton

Notary Public.



15-051-20157-00-00

# WELL LOG

COMPANY **Clinton Oil Company**

SEC. **15** T. **13S** R. **20W**

FARM **Wegele** NO. **1-V**


LOC. **E/2 SW/4 NE/4**

TOTAL DEPTH **3869'**

COUNTY **E111s**

COMM. **11-7-67** COMP. **11-16-67**

CONTRACTOR **Garvey Drilling Company**



CASING **8 5/8" @ 251' w/185 sx**

ELEVATION **2167' KB**

PRODUCTION **D & A**

FIGURES INDICATE BOTTOM OF FORMATIONS

- 75' Rock and Clay
- 252' Blue Shale
- 975' Shale
- 1175' Sand
- 1215' Shale
- 1720' Sand
- 1765' Shale
- 2550' Lime and Shale
- 2590' Shale with Lime
- 3117' Shale and Lime
- 3250' Lime
- 3433' Lime and Shale
- 3869' Lime
- 3869' RTD

**RECEIVED**  
 NOV 27 1967  
 11-27-1967  
 CONSERVATION DIVISION  
 Wichita, Kansas

State of Kansas }  
 County of Barton } SS

I, Sam N. Stephens of Garvey Drilling Company

upon oath state the above and foregoing is a true and correct copy of the log of the Wegele No. 1-V well.

*Sam N. Stephens*

Subscribed and sworn to before me this 22nd day of November 1967

My Commission Expires: May 28, 1969

*Richard H. Dunder*  
 NOTARY PUBLIC

