


15-151-00294-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County. Sec. 36 Twp. 26 Rge. 11 (E) W (W)  
Location as "NE/CNW/SW" or footage from lines SW SW ~~SW~~ NW  
Lease Owner Trans Era Petroleum, Inc.  
Lease Name Martin Well No. 1  
Office Address Russell, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry  
Date well completed 5/4/54 19  
Application for plugging filed 5/2/54 19  
Application for plugging approved 5/2/54 19  
Plugging commenced 5/3/54 19  
Plugging completed 5/3/54 19  
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4518 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	306'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

PLUGGING RECORD

Filled hole with heavy mud to 300', set bottom plug at 300' with one-fourth sack of hulls and 20 sacks of cement used. Filled hole with mud to 40', set top plug at 40' with one-fourth sack of hulls and 10 sacks of cement used. Plug was wired and pushed down.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Trans Era Petroleum, Inc.  
Address Russell, Kansas

STATE OF KANSAS, COUNTY OF RUSSELL, ss.  
H. R. Michaelis (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) H. R. Michaelis  
Russell, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 14th day of May, 1954

My commission expires 1-30-57.

Margie Cooper  
Notary Public.

MAY 10 1954  
OS-18-54  
CONSERVATION DIVISION  
WICHITA, KANSAS

PLUGGING  
FRK SEC 36 T 26 R 11W  
BOOK PAGE 32 LINE 11

Trans Era Petroleum, Inc.  
Martin #1

SW SW NW 36-26-11  
Stafford County, Ks.

Total Depth 4518'  
Comm. 4/14/54  
Comp. 5/4/54

Casing

8 5/8" Set @ 306'

Cement

225 sacks Monarch

Formation	Depth
Sand-clay	110
Red bed	630
Shale	743
Anhydrite	778
Shale	1250
Sand-shale	1510
Lime-shale	3613
Lime	3945
Lime-shale	3978
Lime	4089
Lime--chert	4115
Lime	4138
Lime-shale	4328
Lime-chert	4345
Lime-shale	4406
Sand	4426
Shale	4468
Arbuckle	4495
Lime	4518'

STATE OF KANSAS )  
                          ) ss  
RUSSELL COUNTY )

I hereby certify that the above information is true and correct to the best of my knowledge.

Carol Belf

Subscribed and sworn to before me this 14th day of May, 1954.

**PLUGGING**  
FILE SEC 36 T 26 R 11W  
BOOK PAGE 52 LINE 11

Maizie Cooper  
Notary Public

My commission expires 1-30-57.

RECEIVED  
STAFFORD COUNTY COMMISSIONER  
MAY 15 1954  
CONSERVATION DIVISION