

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-051-249570000

LEASE NAME Arnhold

WELL NUMBER 4

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

3960 Ft. from S Section Line

2310 Ft. from E Section Line

LEASE OPERATOR Oil Producers, Inc. of Kansas

SEC. 16 TWP. 13 RGE. 18 (X or W)

ADDRESS P.O.Box 8647, Wichita, KS 67208

COUNTY Ellis

PHONE#(316) 681-0231 OPERATORS LICENSE NO. 8061

Date Well Completed 4/6/97

Character of Well D&A

Plugging Commenced 4/6/97

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 4/6/97

The plugging proposal was approved on 4/6/97 (date)

by Richard Lacey (KCC District Agent's Name)

Is ACO-1 filled? yes If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom T.D. 3730 Ft.

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Surface		697'	0'	8-5/8"	697'	None

RECEIVED
KANSAS CORP COM
JUN 20 11 10
6-20-97

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged hole with 165 sacks 60/40 Pozmix, 6% gel, 1/4# flocele per sack, as follows: 50 sx @ 1460', 50 sx @ 720', 40 sx @ 350', 10 sx @ 40', 15 sx rathole, 10 sx mousehole. P.D. @ 8:15 am 4/6/97.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Mallard JV, Inc. License No. 4958

Address P. O. Box 1009, McPherson, KS 67460

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Oil Producers, Inc. of Kansas

STATE OF Kansas COUNTY OF Sedgewick, ss.

John S. Weir

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) John S. Weir

(Address) P.O. Box 8647, Wichita, KS 67208



SUBSCRIBED AND SWORN TO before me this 19th day of June, 1997

Diana L. Richecky
Notary Public

My Commission Expires: Jan. 12, 2000

ORIGINAL

MALLARD JV, Inc.
DRILLING CONTRACTORS
P. O. Box 1009
MCPHERSON, KS 67460 316-241-4640

Drillers Log

OPERATOR: **Oil Producers, Inc. of Kansas**
P. O. Box 8647
Wichita, KS 67208

WELL: **Arnhold #4**

API #: 15-051-249570000

COMMENCED: March 31, 1997

LOCATION: **W/2 W/2 NE**
3960' FSL, 2310' FEL
Section 16, Township 13 S, Range 18 W
Ellis County, Kansas

COMPLETED: April 6, 1997

TOTAL DEPTH: 3730'

ELEVATION: 2150' GL, 2155' KB

STATUS: **Dry and Abandoned - Arbuckle Formation**

SPUD: 4:00 pm 3/31/97

SIZE HOLE DRILLED: 12-1/4" x 700'

SURFACE CASING SIZE: 8-5/8" x 23# x 690.78' (18 jts.)

SET AT: 697.38'

CEMENT: 225 sacks HLC, 2% cc, 1/4# flocele per sack, and
125 sacks 60/40 Pozmix, 3% cc, 2% gel

SIZE HOLE DRILLED: 7-7/8" x 3730' RTD

PLUGGED HOLE WITH: 165 sacks 60/40 Pozmix, 6% gel, 1/4# flocele per sack as follows:
50 sx @ 1460'
50 sx @ 720'
40 sx @ 350'
10 sx @ 40'
15 sx rathole,
10 sx mousehole

P. D.: 8:15 am 4/6/97

DRILL STEM TESTS: None

ELECTRIC LOG: Yes

RESERVE PIT: 38,000 ppm chlorides, 500 bbl free fluid content

1997 APR 21 11 05 AM
RECEIVED
KANSAS OIL PRODUCERS