

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD 15-057-21665-00-00

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Ellis County, Sec. 16 Twp. 13s Rge. 17w E/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines

NE-NE-NE

Lease Owner Fred T. Jacobs

Lease Name Hashenberger Well No. 2

Office Address 1000 D. Cody Hays, Kansas 67601

Character of Well (Completed as Oil, Gas or Dry Hole)

Dry Hole

Date Well completed April 7 1979

Application for plugging filed April 7 1979

Application for plugging approved April 7 1979

Plugging commenced April 7 1979

Plugging completed April 7 1979

Reason for abandonment of well or producing formation

Dry Hole

If a producing well is abandoned, date of last production

19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey

Producing formation Depth to top Bottom Total Depth of Well 3588'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface		0'	222'	8 5/8"	222'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

1st. plug at 550' with 70 sacks cement 50-50 Poz. 6% Gel.

2nd. plug at 215' with 20 sacks cement 50-50 Poz. 6% Gel.

3rd. plug at 40' with 10 sacks cement 50-50 Poz 6% Gel.

5 sacks in rathole

RECEIVED  
STATE CORPORATION COMMISSION

MAY 2 1979

5-2-79

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sun Oilwell Cementing, Inc.

STATE OF Kansas COUNTY OF Graham, ss.  
Jerry M. Helberg (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)


Box 32 Morland, Kansas 67650  
(Address)

SUBSCRIBED AND SWORN TO before me this 1st day of April May, 1979

Notary Public.

My commission expires

Dec. 4, 1979



DRILLERS LOG

HASHENBERGER #2

CASING RECORD:

8 5/8" set at 222'

TOTAL DEPTH:

3588'

DESCRIPTION:

NE NE NE  
Sec. 16-13-17, Ellis County, Kansas

OPERATOR: B & F Oil Company

CONTRACTOR: Helberg Oil Company

COMMENCED: March 28, 1979

COMPLETED: April 7, 1979

FORMATION	FROM	TO	REMARKS
			15:05:21 665:00:00
Shale	0	159	
Shale	159	245	
Shale	245	379	
Shale	379	490	
Sand & Shale	490	1005	
Shale	1005	1241	
Anhydrite	1241	1264	
Anhydrite	1264	1274	
Shale	1274	1500	
Shale & Lime	1500	1900	
Shale	1900	1939	
Shale	1939	2053	
Lime & Shale	2053	2240	
Shale & Lime	2240	2350	
Shale & Lime	2350	2490	
Lime	2490	2620	
Lime & Shale	2620	2730	
Lime & Shale	2730	2870	
Lime	2870	2985	
Lime & Shale	2985	3095	
Lime	3095	3175	RECEIVED STATE CORPORATION COMMISSION
Lime	3175	3245	
Lime	3245	3325	MAY - 2 1979
Lime	3325	3390	
Lime	3390	3402	CONSERVATION DIVISION Wichita, Kansas
Lime	3402	3424	
Lime	3424	3470	
Lime	3470	3530	
Lime	3530	3580	
Lime	3580	3588	
T.D.	3588		D & A

I certify that the above is a true and correct copy of the log to the best of my knowledge.

HELBERG OIL COMPANY

*Jerry M. Helberg*  
Jerry M. Helberg

Subscribed and sworn to before me this 1st day of April, 1979.

*Dan W. Richman*  
Notary Public

My commission expires Dec 4, 1979.

