


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

15-057-05539-00-00  
WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Ellis County, Sec. 16 Twp. 13 Rge. 17W (E) (W)

Location as "NE/CNW%SW%" or footage from lines SE NW NE  
Lease Owner Mallonee Drilling Company, Inc.  
Lease Name Catherine Unit "B" Well No. 1  
Office Address 820 Union Center, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed 6-21 19 56  
Application for plugging filed 4-28 19 58  
Application for plugging approved 4-28 19 58  
Plugging commenced 4-28 19 58  
Plugging completed 4-30 19 58  
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production March 10 19 58  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3589 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	137'	None
				5-1/2"	3588'	3027'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked the hole to 3589' and found it open. Filled w/ sand to 3580' and dumped 4 sacks of cement. Pulled casing to 500' and circulated with 25 sacks of mud and pumped in 20 sacks of cement. Pulled casing to 200' and pumped in 20 more sacks of cement. Pulled rest of casing, bailed mud to 35' and ran 10 sacks of cement to base of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Co., Inc.  
Address Chase, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.  
R. E. Mallonee (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. E. Mallonee  
820 Union Center, Wichita, Kansas  
(Address)


SUBSCRIBED AND SWORN to before me this 22nd day of May, 19 58

December 14, 1961

Notary Public.



PLUGGING  
FILE SEC. 16 T. 13 R. 17W  
BOOK PAGE 98 LINE 42



DRILLERS' LOG  
 CATHERINE UNIT "B" #1  
 SE NW NE Sec. 16-13-17W  
 Ellis County, Kansas

CONSERVATION DIVISION  
 WICHITA, KANSAS

15.051.05537.00.00

OWNER: Mallonee Drilling Company, Inc.  
 E. K. Edmiston, et al  
 OPERATOR &  
 CONTRACTOR: Mallonee Drilling Company, Inc.

COMMENCED: 5/31/56  
 COMPLETED: 6/11/56  
 ELEVATION: 2020 K.B.

From	To	Description	Remarks
0	70	Surface soil and clay	
70	137	Blue shale and shells	139.77' 8-5/8" pipe set at 137' with 70 sacks
137	685	Shale and shells	
685	755	Shale, shells and iron pyrites	
755	900	Sand	
900	950	Shale and shells	
950	1170	Shale and sand	
1170	1350	Shale and shells	
1350	1685	Shale and red bed	
1685	1950	Shale and shells	
1950	2915	Shale and lime	DST #1, 3402-32. Open 1 hr. weak blow. 5'OCM and 30' WM. BHP 610#
2915	3037	Shale	
3037	3589	Lime	116 jts. 5 1/2" 14# csg. set at 3588 with 75 sacks
3589		Total depth of hole	
Tops: Topeka			3036 -1016
Heebner			3288 -1287
Lansing			3332 -1312
Arbuckle			3585 -1565
Rotary Total Depth			3589 -1569

I certify that to the best of my knowledge and belief the above represents a true and accurate Drillers' Log record of the captioned well.

*R. E. Mallonee*  
 R. E. Mallonee

STATE OF KANSAS )  
 COUNTY OF SEDGWICK )  
 Subscribed and sworn to before me this 14th day of June, 1956.  
 My commission expires: February 1, 1960

*Barbara J. Layton*  
 Barbara J. Layton, Notary Public

PLUGGING  
 FILE SEC 16 T 13 R 17W  
 BOOK PAGE 98 LINE 42