


STATE OF KANSAS
STATE CORPORATION COMMISSION

15-151-000183-0000

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Pratt County, Sec. 30 Twp. 29S Rge. 11 (W)
Location as "NE/CNW/SW" or footage from lines SE/4 SE/4 NW/4
Lease Owner Monsanto Chemical Company
Lease Name Mico Well No. 1
Office Address P. O. Box 639, Pratt, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed February 28, 19 56
Application for plugging filed February 28, 19 56
Application for plugging approved (Verbal) February 28, 19 56
Plugging commenced February 28, 19 56
Plugging completed February 28, 19 56
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. M. A. Rives
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5169 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	408'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy mud from 5169' to 300' with 20 sacks of cement, heavy mud to 35', Halliburton plug @ 35' with 1/4 sack of hulls and 10 sacks of cement to base of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Garvey Drilling Company
Address 305 East Third Street, Wichita, Kansas

STATE OF KANSAS, COUNTY OF PRATT, SS. J. B. Gibbs (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *J. B. Gibbs*
P. O. Box 639, Pratt, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 1st day of March, 1956

My commission expires September 19, 1959

Merle F. Combs Notary Public.

RECEIVED
CORPORATION COMMISSION
3-2-56
MAR 2 - 1956
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 30 T 29 R 11W
BOOK PAGE 42 LINE 15



WELL LOG

15-151-00083-0000

COMPANY **LION OIL COMPANY**

SEC. 30 T. 29S. 11W

FARM **Mico** NO. **1**


LOC. SE SE NW

TOTAL DEPTH **5169'**

COUNTY **Pratt**

COMM. **February 3, 1956** COMP. **February 28, 1956**

CONTRACTOR **GARVEY DRILLING COMPANY**



CABING **8-5/8" @ 403' w/325 sacks**

ELEVATION **1858 D.F.**

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

70	Clay
95	Sand
350	Shale, Shells & Red Bed
360	Sand
404	Shale, Shell & Red Bed
990	Red Bed
1130	Red Bed & Shale
1170	Anhydrite Streaks & Shale
1310	Shale & Shells
1791	Salt & Shale
1980	Lime & Shale
2125	Lime
3475	Lime & Shale
3515	Lime
3774	Lime & Shale
3808	Lime Shale & Sand
3871	Sand & Shale
3915	Sandy Shale
4450	Lime
4499	Lime & Shale
4544	Lime, Shale & Chert
4576	Lime & Sandy Shale
4589	Lime & Shale
4630	Lime, Shale & Chert
4652	Chert & Lime
4690	Chert
4741	Lime, Shale & Chert
4795	Lime & Shale
4829	Shale & Chert
4911	Lime & Shale
4945	Shale, Chert & Lime
4986	Lime & Shale
5027	Lime, Shale, Chert & Sand
5046	Simpson Sand
5061	Lime & Sand
5076	Sand, Shale & Chert
5116	Lime & Shale
5169	Arbuckle
5169	T.D.

State of **KANSAS**

County of **SEDGWICK**

I, **Robert E. Campbell** of **GARVEY DRILLING COMPANY**

upon oath state that the above and foregoing is a true and correct copy of the log of the **#1 Mico** well

MAR 16 1956

Subscribed and sworn to before me this **14th** day of **Kansas** **March** 19 **56**

My Commission Expires: **September 2, 1959**

Frances Sloan
NOTARY PUBLIC

FRANCES SLOAN, Notary Public
My Commission expires Sept. 2, 1959

PLUGGING
 FILE SEC 30 T 29 R 11W
 BOOK PAGE 42 LINE 15