

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-9-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 32211
Name: O'Brien Energy Resources Corp
Address 1: 18 Congress St. Ste. 207
Address 2: _____
City: Portsmouth State: NH Zip: 03801
Contact Person: Joseph Forma
Phone: (603) 427 2099
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 119-21242500007
Spot Description: _____
52-1/2 SE Sec. 4 Twp. 34 S. R. 29 East West
1320 Feet from North / South Line of Section
1650 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Meade
Lease Name: Larrabee Offset Well #: 2-4
Date Well Completed: _____
The plugging proposal was approved on: 2-21-11 (Date)
by: Eric MacLaren (KCC District Agent's Name)
Plugging Commenced: 2-21-11
Plugging Completed: 2-23-11

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
			20	40	-
			8 5/8	1579	-
			4 1/2	6244	2724

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Mixed 200 lb. hulls + 20 sx cmt. to plug perfs from 5201 to 4941. Shot + pulled 4 1/2 to 1600. Circ. hole w/mud + mixed 50 sx 1600 to 1450 40 sx 600 to 480 10 sx 40 to 0 Capped 8 5/8 3 ft. below G.L.

Plugging Contractor License #: 31151 Name: Sargent And Horton Plugging Inc.
Address 1: Rt 1 Box 49 BA Address 2: _____
City: Tyrone O State: OK Zip: 7395
Phone: (580) 854 6515
Name of Party Responsible for Plugging Fees: O'Brien Energy Resources Corp
State of New Hampshire County: Rockingham, ss. _____
Joseph Forma, Vice President Employee of Operator or Operator on above-described well
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: _____

RECEIVED
MAR 11 2011
KCC WICHITA

SARGENT AND HORTON PLUGGING, INC.

Route 1, Box 49 BA

DON H. HORTON
PHONE (580) 854-6515
Tyrone, OK 73951-9731

PIPE TALLY

From Larrabee Offset 2-4 On 2-23-2011

Tally of 4 1/2 Foot Wt. 10.5

Pipe to _____

	LENGTH		LENGTH		LENGTH		LENGTH		LENGTH		LENGTH	
	FEET	INCH	FEET	INCH	FEET	INCH	FEET	INCH	FEET	INCH	FEET	INCH
1	32	70	32	09	42	56	32	85	33	29		
2	31	54	33	04	29	16	32	60	32	86		
3	30	13	30	99	31	41	33	45	33	33		
4	32	71	32	34	31	35	31	55	33	30		
5	33	—	32	02	29	78	31	90				
6	32	95	32	67	29	64	33	33				
7	33	05	31	75	33	03	29	—				
8	32	20	31	43	31	60	33	18				
9	31	80	32	72	32	62	33	63				
10	31	81	30	26	31	53	33	33				
11	33	25	33	62	31	50	28	75				
12	33	11	33	37	33	37	32	45				
13	32	14	36	63	28	46	32	75				
14	33	18	33	27	32	56	32	92				
15	33	33	31	76	32	98	32	40				
16	32	84	33	64	29	88	31	34				
17	32	71	29	80	32	78	31	58				
18	31	96	32	69	29	35	31	65				
19	32	89	31	—	31	98	33	66				
20	32	59	40	05	32	61	33	76 SJ				

RECEIVED
MAR 11 2011

KCC WICHITA

Tallied By _____

Total Number Joints 84

Total Length 2722 Feet 04 Hundreths _____

BEAVER ACE HOME CENTER
301 DOUGLAS
P.O. BOX 926
BEAVER, OK 73932
PHONE: (580) 625-3192

RECEIVED
MAR 11 2011
KCC WICHITA

ACE, THE HELPFUL HARDWARE FOLKS!

Customer No. 128310	Job No.	Purchase Order No.	Reference	Terms NET 10TH OF MONTH	Clerk GSB	Date 2/21/11	Time 10:11
------------------------	---------	--------------------	-----------	----------------------------	--------------	-----------------	---------------

Sold To
 SARGENT & HORTON PLUGGING, INC.
 RT 1 BOX 49 BA
 TYRONE OK 73951

Ship To
 Larrabee 2-4 2100
 580-651-3005

TERM#601

DOC# 286144/B

 * INVOICE *

TAX : 012 BEAVER

SHIPPED	ORDERED	UM	SKU	DESCRIPTION	SUGG	UNITS	PRICE/PER	EXTENSION
120		EA	PC80	PORTLAND CEMENT #94 * DON'T FORGET PALLET CHG 35 ON PALLET	9.79	120	9.79 /EA	1,174.80 *
1		EA	DOT	DELIVERY CHARGE - OUT TOWN *	75.00	1	75.00 /EA	75.00 *N
				<p><i> Hwy 23 - Kansas state line</i> <i> 10 North to rd X</i> <i> 1 West</i> <i> 1/2 South thru Cattleguard</i> <i> to rig!</i></p>				

** AMOUNT CHARGED TO STORE ACCOUNT **

1,349.66

TAXABLE	1174.80
NON-TAXABLE	75.00
SUBTOTAL	1249.80
TAX AMOUNT	99.86
TOTAL AMOUNT	1349.66

(DON HORTON)

X **Delivery**

Received By

SARGENT AND HORTON
PLUGGING, INC.

Route 1, Box 49BA
Tyrone, OK 73951-9731

DAILY REPORT

No 5047

DATE 2-21-11 FROM 700 TO 500

COMPANY

FARM NO. 2-4

O'Brien Energy Resources Larrabee Offset

HOURS WORKED

NAME

10

D. Horton

10

J. Schoolcraft

10

W. Horton

CONTRACTOR'S TIME _____ COMPANY'S TIME 10

REMARKS: Move on from Forgan. Rig up
pole. Backhoe dug cellar & suction
pit. Unpack casing head. Rig up pump
truck. Mixed 200 lb. hulls & 20 sx
cmt. to plug perfs from 5201 to 4941.
Rig up jacks & shot 4½ @ 4820.

SARGENT AND HORTON
PLUGGING, INC.

Route 1, Box 49BA
Tyrone, OK 73951-9731

No 5048

DAILY REPORT

DATE 2-22-11 FROM 700 TO 500

COMPANY

FARM NO. 2-4

O'Brien

Larrabee Offset

HOURS WORKED

NAME

10

D.H.

10

J.S.

10

W.H.

CONTRACTOR'S TIME 5

COMPANY'S TIME 5

REMARKS: Worked pipe. Lost fluid.
Load 4½. Shot again @ 2724 where
it came loose. Pulled to 1600. Circ.
hole w/mud & mixed 50sx plug
1600 to 1450. Pull to 600. Mixed
40sx 600 to 480. Pulled rest
of 4½.

SARGENT AND HORTON
PLUGGING, INC.

Route 1, Box 49BA
Tyrone, OK 73951-9731

DAILY REPORT

No 5049

DATE 2-23-11 FROM 700 TO 1200

COMPANY

FARM NO. 2-4

O'Brien

Larrabee Offset

HOURS WORKED

NAME

5

D.H.

5

J.S.

5

W.H.

CONTRACTOR'S TIME

COMPANY'S TIME 5

REMARKS: Load hole w/mud to 40.
Mixed 10 sx plug 40 to 0. Load
out jacks. Cut off & capped 8 5/8
3 ft. below G.L. Tore down.