

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 32278
Name: Tengasco, Inc.
Address 1: PO Box 458
Address 2: 1327 Noose Rd
City: Hays State: KS Zip: 67601 + 9744
Contact Person: Gary Wagner
Phone: (785) 625-6374
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
Toronto Depth to Top: 3492 Bottom: 3498 T.D. 3906
Marmaton Depth to Top: 3844 Bottom: 3850 T.D. 3906
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 195-20489-00-00
Spot Description: _____
NE SW NE Sec. 9 Twp. 13 S. R. 21 East West
1,650 Feet from North / South Line of Section
1,650 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Trego
Lease Name: Keller A Well #: 1
Date Well Completed: 9-25-78
The plugging proposal was approved on: 3-23-11 (Date)
by: Marvin Mills (KCC District Agent's Name)
Plugging Commenced: 3-24-11
Plugging Completed: 3-24-11

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8-5/8"	258'	N/A
		Production	4-1/2"	3906'	N/A

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran tbg to 3800', spotted 100 sx cmt w/ 200# hulls on bottom. Pulled tbg to 2400' Circulated cmt to surface w/ 155 sx. Pulled tbg & topped of csg w/ 35 sx. Tied on 8-5/8" & squeezed in 5 sx to 400#. 295 total sx 60/40 4% gel.

RECEIVED

MAR 29 2011

KCC WICHITA

Plugging Contractor License #: 32332 Name: Fischer Well Service
Address 1: PO Box 733 Address 2: _____
City: Hays State: KS Zip: 67601 + 0733
Phone: (785) 628-3837
Name of Party Responsible for Plugging Fees: Tengasco, Inc.
State of Kansas County, Ellis, ss.
Gary Wagner Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Gary Wagner