

Notice: Fill out COMPLETELY  
and return to Conservation Division at  
the address below within  
60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 30458  
Name: RJM Oil Company, Inc.  
Address 1: P.O. Box 256  
Address 2: \_\_\_\_\_  
City: Claflin State: KS Zip: 67525 + \_\_\_\_\_  
Contact Person: Chris Hoffman  
Phone: (620) 786-8744  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (if needed attach another sheet)  
\_\_\_\_\_- Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_- Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_- Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15 - 009-25340-00-00  
Spot Description: \_\_\_\_\_  
S/2 NW, SE, NW Sec. 21 Twp. 16 S. R. 11  East  West  
1,665 Feet from  North /  South Line of Section  
1,650 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Barton  
Lease Name: Nadine Well #: 1  
Date Well Completed: 09/18/2009  
The plugging proposal was approved on: 11/18/2010 (Date)  
by: Case Morris (KCC District Agent's Name)  
Plugging Commenced: 03/17/2011  
Plugging Completed: 03/18/2011

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8-5/8"	436'	0'
		Production	5-1/2"	3333'	1729

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

03/17/11 - Drove to location. Tailgate safety meeting. Rig up. Unpack Braden head. Wait on water truck. Sand well up to 3100'. Dump 220 scoops. Took 45 bbls of water to load hole. Rig up bailer. Set casing jacks & 5-1/2" equipment while sand falls to bottom. Run down - tag sand w/bailer. Tag @ 3100'. Mix 5 sacks of cement. Run bailer 3 times to dump all 5 sacks on top of sand. Rig down bailer. Pull slips. Pull the stretch - 6-1/4". Clean tools. Shut down for day. Drive back to shop.

03/18/11 - Drove to location. Tailgate safety meeting. Rig up perforators. Run down - shoot casing off @ 1729'. Fluid @ 300'. Rig down perforators. Pull casing free w/jacks. Pull 5 jts. Set 1st plug @ 1500'. Wait 2-1/2 hrs on cementers. Dump 125 sacks 60/40 4% gel cement w/300# cotton seed hulls. Pull 18 more jts. Set 2nd plug @ 750'. Dump 30 sacks 60/40 4% gel cement w/100# cotton seed hulls. Pull 7 more jts. Set 3rd plug @ 475'. Dump 40 sacks 60/40 4% gel cement w/100# cotton seed hulls. Pull 6 more jts. Set 4th plug @ 200'. Dump 75 sacks 60/40 4% gel cement to circulate to surface. Pull last 5 jts. Grand total of 41 - 5-1/2" jts. Recovered - top off w/10 sacks 60/40 4% gel cement. Tally casing @ each plug. Rig down cementers. Rig down casing jacks. Rig down. Load jacks. Drive equipment back to shop.

Plugging Contractor License #: 6901 Name: D.S. & W. Well Servicing, Inc.  
Address 1: 1822 24th Street Address 2: \_\_\_\_\_  
City: Great Bend State: Kansas Zip: 67530 + \_\_\_\_\_  
Phone: (620) 793-5838  
Name of Party Responsible for Plugging Fees: RJM Oil Company, Inc.  
State of Kansas County, Barton, ss.  
Tim Dickson  Employee of Operator or  Operator on above-described well,  
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Tim Dickson

RECEIVED

MAR 28 2011

KCC WICHITA