

15-145-20587-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Pawnee County. Sec. 19 Twp. 22S Rge. 17W E/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines _____

C SE NE

Lease Owner Zenith Drilling Corporation, Inc.
Lease Name Eikmeier #1 Well No. 1
Office Address Suite 600, 200 West Douglas, Wichita, Ks 67202
Character of Well (Completed as Oil, Gas or Dry Hole) _____

Dry Hole


Date Well completed April 10, 1979 19
Application for plugging filed April 9, 1979 19
Application for plugging approved April 9, 1979 19
Plugging commenced 4:00 AM, April 10, 1979 19
Plugging completed 6:00 AM, April 10, 1979 19
Reason for abandonment of well or producing formation _____

Dry Hole

If a producing well is abandoned, date of last production _____ 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4240'
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plot

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	255'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed; from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud.
50 sacks 50/50 Pozmix with 2% gal thru open end drill pipe at 420'. 25 Sacks thru open end drill pipe at 240'. Solid bridge, 1/2 sack hulls and Howco plug at 40'. 10 sacks to surface. 2 sacks in rat hole.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sterling Drilling Company, P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.
F. A. Wuellner (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

STERLING DRILLING COMPANY
(Signature) [Signature]
F. A. Wuellner, Secretary
P. O. Box 129, Sterling, Kansas 67579
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of April, 19 79



Charles M. Hall
Charles M. Hall, Notary Public.

RECEIVED
STATE CORPORATION COMMISSION

APR 16 1979

CONSERVATION DIVISION
Wichita, Kansas

My commission expires _____

15-145-20587-0000

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

WELL LOG ----- FINNMEIER #1
Located: C SE NE, Section 19-22S-17E, Pawnee County,
Kansas

OWNER: Zenith Drilling Corporation
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: April 2, 1979
COMPLETED: April 10, 1979

TOTAL DEPTH: 4240'

<u>LOG</u>	<u>CALIBER RECORD</u>
0 - 105 Clay, Shale	Ran 6 joints new 8 5/8", 23" casing, 241.16' set at 255' K.B. Cemented with 250 sacks 60/40 Pozmix with 3% cc. Plug down at 4:30 AM, 4-3-79, by Halliburton.
105 - 280 Shale	
280 - 1027 Shale - Sand	
1027 - 1150 Anhydrite	
1150 - 1950 Shale	
1950 - 3010 Shale and Lime	
3010 - 3880 Lime	
3880 - 3990 Lime and Shale	
3990 - 4240 Lime	Plugged.

RECEIVED
STATE CORPORATION COMMISSION
APR 16 1979
CONSERVATION DIVISION
Wichita, Kansas