


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Ellis County, Sec. 5 Twp. 14S Rge. 19 (E) (W)

Location as "NE/CNW/SE/SW" or footage from lines SE SW SW
Lease Owner Clinton Oil Co.
Lease Name Gus Riedel "B" Well No. 2
Office Address 217 No. Water, Sichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed October 30 19 56
Application for plugging filed August 14 19 73
Application for plugging approved August 15 19 73
Plugging commenced August 24 19 73
Plugging completed August 24 19 73
Reason for abandonment of well or producing formation Depletion



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production July 18 19 73
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation Arbuckle Depth to top 3853' Bottom 3874' Total Depth of Well 3927' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	273'	None
				5 1/2"	3925'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Spotted 30 sks 50 - 50 pozmix in 5 1/2" csg fm 3877' - 3800'.

Spotted 4 sks hulls and 26 sks gel fm 3800' - 600'.

Spotted 50 sks 50-50 pozmix 600' to surface.

Pmpd 20 sks 50-50 pozmix down annulus 200' to surface.

RECEIVED
STATE CORPORATION COMMISSION
SEP 5 1973

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sun Oil Well Cementing, Inc.
Address P. O. Box 169, Great Bend, Kansas 67530

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Ronald E. Rowe (employee of owner) or (owner or operator) of the above-described


well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well, as filed and that the same are true and correct. So help me God.

(Signature) Ronald E. Rowe Ronald E. Rowe
217 North Water, Wichita, Kansas 67202
(Address)

Subscribed and sworn to before me this 4th day of September, 19 73

Shirley A. McGuire Shirley A. McGuire
Notary Public.

My Commission Expires December 2, 1973



Well File

15-051-03033-0000

ROTARY DRILLING LOG

OPERATOR: Stanolind Oil & Gas Co.
Gus Riedel "B" #2
Ellis County, Kansas

CONTRACTOR: Prime Drilling Company
CO COMM: 10-13-56
COMP: 10-31-56

Formations:

Remarks: Set 8 5/8" surface casing
at 213' cemented with 150 sacks pozmix,
2% C. C.

Surface Clay & Sand	120'
Shale & Shells	495'
Sand	630'
Shale	825'
Shale & Shells	915'
Shale & Sand	975'
Sand	1290'
Shale & Red Bed	1501'
Anhydrite	1548'
Shale & Shell	2080'
Shale & Lime	3140'
Lime	3475'
Lime & Shale	3528'
Lime	3793'
Lime & Shale	3829'
Corring	3886'
Lime & Shale & Chert	3910'
Dolomite	3926'
Rotary Total Depth	3926'



Set 5-1/2" casing at 3925' with
200 sacks special Portland cement.

We certify the above log is true
and correct to the best of our
knowledge and belief.

PRIME DRILLING COMPANY

R. R. McNicol

R. R. McNicol

RECEIVED
STATE CORPORATION COMMISSION

AUG 15 1973

CONSERVATION DIVISION
Wichita, Kansas