

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 34357
Name: Atlas Operating LLC
Address 1: 15603 Kuykendahl RD STE # 200
Address 2: _____
City: Houston State: TX Zip: 77090 + 3655
Contact Person: Robert Younce
Phone: (620) 243-4092
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Mississippi Depth to Top: 4247 Bottom: _____ T.D. 4297
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 095-10021-00-00
Spot Description: _____
SW NE NE Sec. 6 Twp. 30 S. R. 8 East West
990 Feet from North / South Line of Section
990 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Kingman
Lease Name: Pomeroy Well #: 1-6
Date Well Completed: 09/16/58
The plugging proposal was approved on: _____ (Date)
by: _____ (KCC District Agent's Name)
Plugging Commenced: 02/16/11
Plugging Completed: 02/17/11

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
MISSISSIPPI	Gas, Oil and Water	Surface	8 5/8	327	None
		Production	5 1/2	4247	2630

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Checked hole sand at 4195' & bailed 5 sacks cement on sand. Ripped casing at 2810' & 2630' pipe came free at 2630'. Pulled casing up to 1300' & pumped 35 sacks cement, 3 % cc & 100# hulls. Pulled to 850' & pumped 35 sacks cement & 100 hulls. Pulled to 360' & pumped 110 sacks cement to surface. Pulled rest of casing.

Plugging Contractor License #: 31925 Name: Quality Well Service, INC
Address 1: 190 US HWY 56 Address 2: _____
City: Ellinwood State: KS Zip: 67526 + _____
Phone: (620) 727-3410
Name of Party Responsible for Plugging Fees: Atlas Operating, LLC
State of TX County, Harris, ss.
Ramy H. Farrag Employee of Operator or Operator on above-described well.
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Ramy H. Farrag

RECEIVED


Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

APR 08 2011

KCC WICHITA

AP

ATLAS OPERATING LLC



April 4, 2011


Kansas Corporation Commission
Conservation Division
130 S. Market, room 2078
Wichita, KS 67202-3802

Dear Mr. or Madam,

Atlas Operating LLC is submitting CP-4 well plugging record for the Pomeroy # 1 Lease
API # 15-095-10021-00-00

If additional information required please advise

Sincerely,


Ramy H. Farrag
Production Coordinator

Cc: Well Files
Regulatory Files

RECEIVED
APR 08 2011
KCC WICHITA