

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

Form CP-4
March 2009

Type or Print on this Form
Form must be Signed
All blanks must be Filled

WELL PLUGGING RECORD

K.A.R. 82-3-117

OPERATOR: License #: 34506
 Name: EMPIRE ENERGY E&P, LLC
 Address 1: 17 ARENTZEN BLVD, SUITE 203
 Address 2: _____
 City: CHARLEROI State: PA Zip: 15022 + _____
 Contact Person: DAVID STAHL
 Phone: (785) 434-6245
 Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (If needed attach another sheet)
ARBUCKLE Depth to Top: 3734 Bottom: 3796 T.D. 3880'
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 009-24361-00-00
 Spot Description: _____
 SW NE NE Sec. 18 Twp. 20 S. R. 15 East West
4,290 Feet from North / South Line of Section
2,310 Feet from East West Line of Section
 Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
 County: BARTON
 Lease Name: DECKERT "C" Well #: 2-18
 Date Well Completed: _____
 The plugging proposal was approved on: 3-16-2011 (Date)
 by: CASE MORRIS (KCC District Agent's Name)
 Plugging Commenced: 3-18-11
 Plugging Completed: 3-21-11

Show depth and thickness of all water, oil and gas formations.

| Oil, Gas or Water Records | | Casing Record (Surface, Conductor & Production) | | | |
|---------------------------|---------|---|--------|---------------|------------|
| Formation | Content | Casing | Size | Setting Depth | Pulled Out |
| | | SURFACE | 8-5/8" | 1057' | NONE |
| | | PRODUCTION | 5-1/2" | 3883' | 1800' |
| | | | | | |
| | | | | | |

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

SAND @ 3675', BAILED 5 SX CEMENT ON SAND. RIPPED CSG @ 2040' & 1800': PIPE CAME FREE @ 1800'. PULLED CSG UP TO 1600', PUMPED 125 SX CEMENT & 300# HULLS. PULLED CSG TO 1075', PUMPED 40 SX CEMENT & 100# HULLS. PULLED CSG UP TO 650', PUMPED 60 SX CEMENT & 100# HULLS. PULLED CSG UP TO 150', PUMPED 90 SX CEMENT TO SURFACE.

Plugging Contractor License #: 31925 Name: QUALITY WELL SVC, INC
 Address 1: 190 US HWY 56 Address 2: _____
 City: ELLINWOOD State: KS Zip: 67526 + _____
 Phone: (620) 727-3410
 Name of Party Responsible for Plugging Fees: EMPIRE ENERGY E&P, LLC
 State of KANSAS County: BARTON ss. Rickey Pop
RICKEY POPP Employee of Operator or Operator on above-described well,
 (Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Rickey Pop

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
APR 08 2011
KCC WICHITA

AR