

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

Form CP-4
March 2009

Type or Print on this Form
Form must be Signed
All blanks must be Filled

WELL PLUGGING RECORD
K.A.R. 82-3-117

OPERATOR: License #: 34506
Name: EMPIRE ENERGY E&P, LLC.
Address 1: 17 ARENTZEN BLVD, SUITE 203
Address 2: _____
City: CHARLEROI State: PA Zip: 15022 + _____
Contact Person: DAVID STAHL
Phone: (785) 434-6245
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
ARBUCKLE Depth to Top: 3794 Bottom: 3804 T.D. 3920
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 009-24306-00-00
Spot Description: _____
SE - NE NE Sec. 18 Twp. 20 S. R. 15 East West
4,290 Feet from North South Line of Section
330 Feet from East West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: BARTON
Lease Name: DECKERT "C" Well #: 1-18
Date Well Completed: _____
The plugging proposal was approved on: 3-21-2011 (Date)
by: CASE MORRIS (KCC District Agent's Name)
Plugging Commenced: 3-22-11
Plugging Completed: 3-23-11

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		SURFACE	8-5/8"	1105'	NONE
		PRODUCTION	5-1/2"	3917'	2030'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

SAND @ 3700', BAILED 5 SX CEMENT ON SAND. RIPPED CSG @ 2210' & 2030': PIPE CAME FREE @ 2030'. PULLED CSG UP TO 1600', PUMPED 125 SX CEMENT & 300# HULLS. PULLED CSG TO 1075', PUMPED 40 SX CEMENT & 100# HULLS. PULLED CSG UP TO 650', PUMPED 60 SX CEMENT & 100# HULLS. PULLED CSG UP TO 150', PUMPED 75 SX CEMENT TO SURFACE.

Plugging Contractor License #: 31925 Name: QUALITY WELL SVC, INC
Address 1: 190 US HWY 56 Address 2: _____
City: ELLINWOOD State: KS Zip: 67526 + _____
Phone: (620) 727-3410
Name of Party Responsible for Plugging Fees: EMPIRE ENERGY E&P, LLC
State of KANSAS County, BARTON, ss.
RICKEY POPP Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Rickey Popp

RECEIVED
APR 08 2011
KCC WICHITA

DR