

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

15:051-23486-00-00
WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Ellis SEC. 23 TWP. 13 RGE. 18 E/W
Location as in quarters or footage from lines:
SE 1/4 990 FNL 330 FWL

Lease Owner S & V Oil Inc.
Lease Name' Witt Well No. 1 (one)
Office Address Box 857 Russell, Kansas 67665
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
Date Well Completed 6-22-83
Application for plugging filed 6-22-83
Plugging commenced 6-22-83 10:15 am
Plugging completed 6-22-83 2:15 pm
Reason for abandonment of well or producing formation Dry Hole

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor
Producing formation _____ Depth to top _____ bottom T.D. 3720

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Filled hole to 1450 with heavy mud and mixed 25 sacks of cement and pumped in hole thru
drill pipe.

Filled hole to 700 with heavy mud and mixed 70 sacks of cement and pumped in hole thru
drill pipe.

Filled hole to 40 built solid bridge pushed down plug and mixed 10 sacks and filled hole
to bottom of cellar; mixed 10 sacks and pumped into the rat hole.

All cement used was 50-50 Poz Mix 6 % Gel 2% CC

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Revlin Drlg., Inc.

STATE OF Kansas COUNTY OF Russell, ss.

Stanley C. Lingreen (employee of owner) or ~~(owner or operator)~~ of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.



(Signature) Stanley C. Lingreen
Box 293 Russell, Kansas 67665
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of June, 1983

My Commission expires: November 10, 1984

Paula J. Gibson
Notary Public.
STATE CORPORATION COMMISSION

JUN 27 1983
6-27-83
CONSERVATION DIVISION
Wichita, Kansas