

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Bldg.  
 Wichita, Kansas 67202

Form CP-4  
 Rev. 12-15-80

15051214650000  
 WELL PLUGGING RECORD

Give All Information Completely  
 Make Required Affidavit

COUNTY Ellis SEC. 23 TWP. 13 RGE. 18 E/W  
 Location as in quarters or footage from lines:  
C - N $\frac{1}{2}$  - SW - NE

		o	

Locate Well  
 correctly on above  
 Section Platt.

Lease Owner Dreiling Oil, Inc.  
 Lease Name Leiker Well No. 3  
 Office Address Rt. #1, Victoria, KS 67671  
 Character of Well (Completed as Oil, Gas or Dry Hole): Oil  
 Date Well Completed 4-12-78  
 Application for plugging filed 3-30-82  
 Plugging commenced 4-20-78  
 Plugging completed 4-20-78  
 Reason for abandonment of well or producing formation depleted

Was permission obtained from the Conservation Division or it's  
 Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Scheck  
 Producing formation Kansas City Depth to top \_\_\_\_\_ bottom T.D. 3788'  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
Surface Pipe				8 5/8"	167'	0'
Casing				4 1/2"	3,787'	960'

Describe in detail the manner in which the well was plugged, indicating where the mud  
 fluid was placed and the method or methods used in introducing it into the hold. If cement  
 or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
 to \_\_\_\_\_ feet for each plug set.

Plugged with 4 sacks hulls, 15 sacks gel, 70 sacks cement, 4 sacks gel, 1 sack hulls,  
 8 5/8" plug and 70 sacks cement. Squeeze pressure 500#.


RECEIVED  
 STATE CORPORATION COMMISSION  
 APR 21 1982  
 CONSERVATION DIVISION  
 WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)  
 Name of Plugging Contractor Dreiling Oil, Inc.

STATE OF KANSAS COUNTY OF ELLIS, ss.  
Bill Draper (employee of owner) or (owner or operator) of the  
 above-described well, being first duly sworn on oath, says: That I have knowledge of the  
 facts, statements, and matters herein contained and the log of the above-described well as  
 filed and that the same are true and correct. So help me God.

(Signature) Bill Draper  
Victoria, KS 67671  
 (Address)

SUBSCRIBED AND SWORN TO before me this 21st day of April, 19 82



Cecilia Basgall  
 Cecilia Basgall Notary Public.

My Commission expires: 1-19-85

# DREILING OIL, INC.

Victoria, Kansas 67671

## WELL LOG

Dreiling Oil, Inc.  
Rt. #1  
Company Victoria, KS 67671  
Farm Leiker No. 3  
Total Depth 3,788'  
Comm. 4-5-78 Comp. 4-12-78  
Contractor Dreiling Oil, Inc.  
Rt. #1  
Victoria, KS 67671

Sec. 23 Twp. 13 Rng. 18  
Location C-N $\frac{1}{2}$  - SW - NE  
County Ellis  
Elevation: 2146 K. B.  
2143 D. F.  
2141 G. R.

15051-21465-00-00

Casing Record  
167' - 8 5/8"  
3,787' - 4 1/2"

Cement Record  
130 sacks cement  
cemented w/225 sacks

Production:

Figures Indicate Bottom of Formations


0'  
172'  
889'  
1390'  
1434'  
1785'  
3315'  
3788'

172'  
889'  
1390'  
1434'  
1785'  
3315'  
3788'  
T.D.

Shale  
Shale  
Shale & Sand  
Anhydrite  
Shale  
Shale & Lime  
Lime

STATE OF KANSAS)  
                          )ss  
COUNTY OF ELLIS)

I, Joseph A. Hess, Secretary Treasurer of Dreiling Oil, Inc.,  
upon oath states that the above and foregoing is a true and correct  
copy from the Daily Drilling Report from the Leiker #3.

  
JOSEPH A. HESS

Subscribed and sworn to before me this 19th day of April, 1978.

  
Cecilia Basgall Notary Public

CECILIA BASGALL  
NOTARY PUBLIC  
Ellis County, Kansas

My appointment expires: November 17, 1980.

RECEIVED  
STATE CORPORATION COMMISSION

MAR 31 1978  
CONSERVATION DIVISION  
Wichita, Kansas